



NOTE
 TOPOGRAPHICAL SURVEY BASED ON TRINITY SURVEYS PROJECT TS 2527 - T-01, DATE RECEIVED 02.08.2021.
 ADDITIONAL TOPOGRAPHICAL SURVEY BASED ON GRANITE CITY SURVEYS PROJECT 'GCS6888 - T-01', DATE RECEIVED 26.07.2023.

WATER MAIN LEGEND

	DENOTES EXISTING WATER MAIN.
	DENOTES EXISTING HYDRANT.
	DENOTES EXISTING CONTROL VALVE.
	DENOTES EXISTING CAPPED END.
	DENOTES PROPOSED WATER MAIN.
	DENOTES FIRE HYDRANT.
	DENOTES SCOUR HYDRANT.
	DENOTES CONTROL VALVE.
	DENOTES DOUBLE CHECK VALVE.
	DENOTES PROPOSED STOPCOCK.
	DENOTES WATER METER.
	DENOTES DUCTING.

REMAINING 3ND RESIDENTIAL HOMES WILL HAVE INDIVIDUAL FIREFIGHTING APPROVALS SOUGHT DURING BUILDING WARRANT STAGE. IT IS PROPOSED THAT 5000 LITRE TANKS WILL BE INSTALLED AT EACH HOME.

5000 LITRE UNDERGROUND TANK INSTALLED FOR FIREFIGHTING FOR THIS PLOT. APPROVAL RECEIVED.

RIVER GAI RN

NOT FOR CONSTRUCTION

GENERAL NOTES:-
 THE CONTRACTOR MUST CONSULT THE CIVIL/STRUCTURAL DESIGN ENGINEER IMMEDIATELY IF:
 a) GROUND CONDITIONS VARY ON SITE.
 b) EXISTING BUILDINGS VARY ON SITE.
 c) DIMENSIONS OR LEVELS SHOWN ARE CHANGED BY ANYONE ON SITE.
 d) COMPLETE OR PARTIALLY COMPLETE STRUCTURES ARE TO BE SUBJECT TO CONSTRUCTION LOADING OR AFFECTED BY TEMPORARY WORKS.
 DO NOT SCALE - IF IN DOUBT, ASK.
 LARGE SCALE DETAILS TAKE PRECEDENCE OVER SMALL SCALE DETAILS.
 ALL MATERIALS ARE TO BE USED STRICTLY IN ACCORDANCE WITH MANUFACTURERS INSTRUCTIONS.
 THE CONTRACTOR WILL BE RESPONSIBLE FOR ALL COSTS INVOLVED IN CHANGES OR MODIFICATIONS REQUESTED AND APPROVED, TO SUIT HIS PREFERRED WORK METHOD.
 ALL NECESSARY METHOD STATEMENTS MUST BE PROVIDED PRIOR TO COMMENCEMENT OF ASSOCIATED SITE OPERATIONS.
 THIS DRAWING SHOULD ONLY BE USED FOR CONSTRUCTION PURPOSES WHEN THE ISSUE STATUS IS 'FOR CONSTRUCTION'.
 ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE STATED.
 ALL LEVELS ARE IN METERS UNLESS OTHERWISE STATED.

© THE COPYRIGHT OF THIS DRAWING SUBSISTS WITH RAMSAY & CHALMERS

Rev.	By	App.	Description	Date
B	NJR		INITIAL ISSUE	25.10.2023
A	JCB		INITIAL ISSUE	15.09.2023

Project: **SITE ADJACENT TO WATERWORKS BRIDGE OF GAI RN, BALLATER.**

Drawing Title: **PLOTS 1-4 WATER SUPPLY.**

Client: **INVERCAULD ESTATE**

Drawing ID: **XXX-RAC-ZZ-XX-DR-C-0010-B**

Job No:	Scale	Issue Status
C5843	1:500 - A1 1:1000- A3	FOR PLANNING

Ramsay & Chalmers
 Consulting Structural & Civil Engineers
 Chaitan Mews Offices, 18 Chaitan Place, Aberdeen, AB10 6RD
 01224 560700
 www.ramsaychalmers.co.uk

CONNECTION DETAILING TO BE CONFIRMED BY SCOTTISH WATER.

NON RETURN VALVE.

PROPOSED SLUICE VALVE TO HELP LOCATE REDUCER IN FUTURE.

PROPOSED 110/90mm REDUCER.

PROPOSED 90mm WATER MAIN

PROPOSED ADVANCED TIE IN WORKS TO THIS POINT.

PROPOSED 90mm WATER MAIN

A93