



18 degree Redland 49 concrete tiled roof to match main roof

1600 x 940 mm Velux window

instal brown vertical timber boarding over existing wall to first floor of elevation

remove window block up & make good instal 600 wide x 1550 high black upvc window with opening toplight to match existing

25 degree Redland 49 concrete tiled roof to match main roof

1000 wide x 1500 mm high black upvc double glazed corner window

76 mm round upvc rainwater downpipe taken to new soakaway 5000 from any building in garden 1 metre below inver of pipe Crate system wrapped in Geo Tech type material

remove door block up & make good instal 600 wide x 1550 high black upvc window with opening toplight to match existing

connect 110 mm toilet, 50 mm washbasin shower waste pipes to 110 mm stub stack connected to new soilrun taken to new manhole provide access at all changes in direction of pipe run & at base of soil pipe

pointed rendered 100 mm blockwork to match existing 100 mm filled cavity wall & blockwork plasterboard on dabs inner skin

PLANNING APPLICATION

REVISION _____ DATE _____

ARCHITECT
TA ARCHITECTS
 11 JOYDENS WOOD ROAD BEXLEY
 KENT DA5 2HS Tel 07905 130591
 ta140256@googlemail.com

JOB
 PROPOSED GROUND FLOOR
 REAR EXTENSION AND PORCH
 AT 170 UPTON ROAD SOUTH
 BEXLEY KENT DA5 1QR

DRAWING
 PROPOSED SIDE ELEVATION
 FACING No 172 UPTON ROAD
 SOUTH

SCALE 1:50 AT A3 DATE OCT 2023

DRAWING NO.
 ME/07

