



insert lintolcut down to form window opening
& instal black upvc window with opening toplight
to match existing

connect 50 mm sinks washing machine
waste pipes to existing gully provide access
at all changes in direction of pipe run

insert lintolcut down to form door opening
& instal 2100 high x 900 wide half glazed
white upvc door

pointed rendered 100 mm blockwork
to match existing 100 mm filled cavity
wall & blockwork plasterboard on dabs
inner skin

instal brown vertical timber boarding over existing
wall to first floor of elevation

18 degree Redland 49 concrete tiled roof
to match main roof

1600 x 940 mm Velux window

PLANNING APPLICATION

REVISION	DATE
ARCHITECT	
TA ARCHITECTS 11 JOYDENS WOOD ROAD BEXLEY KENT DA5 2HS Tel 07905 130591 ta140256@googlemail.com	

JOB
PROPOSED GROUND FLOOR REAR EXTENSION AND PORCH AT 170 UPTON ROAD SOUTH BEXLEY KENT DA5 1QR

DRAWING
PROPOSED SIDE ELEVATION FACING No 168 UPTON ROAD SOUTH

SCALE	DATE
1:50 AT A3	OCT 2023

DRAWING NO.
ME/09

