

Room 211 highlighted red

■ Proposed extract grille terminal indicated - rubble dressed back 12mm deep to allow the grille to finish flush with the face of the rubble. Grille mechanically fixed with plugs and SS screws/washers and pointed all round in lime mortar.

✓ Remove existing cast iron branch and replace with 100mm dia cast iron connected to existing WVP which is to be renewed in 100mm cast iron soil quality pipe.
Repaint cast iron - prime / undercoat and gloss paint colour 08 B 21



client
NEWBATTLE ABBEY COLLEGE

job
**Newbattle Abbey College
Capital Projects**

scale drawn date
As figured dw 10/23

drawing
**Proposed Accessible WC
EAST ELEVATION indicating
proposed alterations**

STATUTORY CONSENT SUBMISSION

letter revision by date



W 1834 /AC / I. 01