




EAST ELEVATION




Room 211 highlighted red

Proposed extract grille terminal indicated - rubble dressed back 12mm deep to allow the grille to finish flush with the face of the rubble. Grille mechanically fixed with plugs and SS screws/washers and pointed all round in lime mortar.

Remove existing cast iron branch and replace with 100mm dia cast iron connected to existing WVP which is to be renewed in 100mm cast iron soil quality pipe. Repaint cast iron - prime / undercoat and gloss paint colour 08 B 21.

This copy has been made by or with the authority of Midlothian Council pursuant to Section 47 of the Designs and Patents Act 1988. Unless that Act provides a relevant exception to copyright, the copy must not be copied without the prior permission of the copyright owner.



client NEWBATTLE ABBEY COLLEGE	scale 1 / 200	drawn dw	date 10/23
	drawing EAST ELEVATION Proposed Accessible WC Room 211		
job Newbattle Abbey College Capital Projects	LBC Submission		
	letter	revision	by date
			 CLWG Orlinon Lang, Willis + Galloway Architects <small>38 Dean Park Mews Edinburgh EH4 1ED Telephone 0131 315 2940 www.CLWG-Architects.com</small>
			W 1834 /23 / 03