

GROUND ASSESSMENT REPORT & DRAINAGE RECOMMENDATIONS

PROPOSED 3 NEW DWELLINGHOUSES LAND AT MILL OF KINCARDINE FETTERCAIRN LAURENCEKIRK ABERDEENSHIRE AB30 1HA

Clients: Tulloch Farm

Architects: A.B Roger & Young Ltd

Contract No.: 3386/23

Report Issued: 21 June 2023

CONTENTS

Introduction

Site Location & Brief Description

Site Work Trial Pits Percolation Testing Infiltration Testing

Ground Assessment
Published Geology
Encountered Ground Conditions
Groundwater Observations

Discussion
Sub-Soils
Sewage Treatment
Foul Water Discharge
SuDS & Surface Waters

Drainage Recommendations Foul Water Discharge SEPA Surface Water Disposal Storm Cells Add Ring Proposed Drainage

System Maintenance Sewage Treatment System Soakaways

Regulations

Foundation Recommendations Safe Bearing Capacity Settlement De-watering

APPENDIX A

Site Plans Fig. 1. General & Site Location Plans

Fig. 2. Test Location Plan

Trial Pit Logs TP1 – TP4

Drainage Fig. 3. Proposed Drainage Layout

Fig. 4. Indicative Foul water Soakaway Construction

Fig. 5. Indicative Storm Cell Installation

Certificates Foul Water Discharges

Surface Water Disposal

GROUND ASSESSMENT & DRAINAGE RECOMMENDATION REPORT

PROPOSED 4 NEW DWELLINGHOUSES LAND AT MILL OF KINCARDINE FETTERCAIRN, LAURENCEKIRK ABERDEENSHIRE, AB30 1HA

INTRODUCTION

At the request of A.B Roger & Young Ltd on behalf of Tulloch Farm, a ground assessment investigation was undertaken on land at Mill of Kincardine, Fettercairn, north of Laurencekirk, Aberdeenshire.

It is proposed to demolish the existing redundant and storm damaged buildings and erect three new dwellinghouses on the site.

The purpose of the visit was to carry out a ground investigation to determine the nature of the materials underlying the area of the site and to undertake the following: -

- to assess the underlying ground conditions
- to carry out percolation testing to assess the suitability of the underground strata for the disposal of effluent from a sewage treatment system to the ground via a designed sub-surface soakaway system
- to carry infiltration testing for the disposal design for surface waters from the proposed development

SITE LOCATION & BRIEF DESCRIPTION

The site is located on land at Mill of Kincardine, Fettercairn, north of Laurencekirk with access off the B974 and B966 and local roads on land all under the ownership of the applicant, OS Grid Ref NO 69354 75907 (approx. centre of site), see Fig. 1. General & Site Location Plans.

The proposed development site is occupied by the existing redundant farm buildings and large areas of concrete. The site has a general fall to the south-west.

The site is serviced by, mains water, electricity and telephone. The existing cottages are served by a shared septic tank located in the garden to the south-east. There is no mains sewer available for the proposed development.

There are no known wells supplying potable water within 50m of the site. There are no watercourses within 10m of the site. The Devilly Burn flow >200m to the west of the site.

SITE WORK

Trial Pits

On the 26th May 2023, a tracked excavator with a 0.90m bucket excavated trial pits to carry out an assessment of the underlying ground conditions, to carry out infiltration testing in the areas of the potential surface water sub-surface soakaways.

The locations of the trial pits were decided on site taking into account the site topography and indicated development layout and are all indicated on Fig. 2. Test Location Plan in Appendix A.

Percolation Testing

Percolation testing was carried out in test holes adjacent to observation trial pits TP1 & TP3 and TP4 in accordance with Section 3.9 of the Scottish Building Standards Technical Handbook (Domestic) and SEPA CAR Regulations. The test results are shown on the following table: -

Date of Testing 26/5/22	TP1	TP3	
Average time taken for water to drain 3 times in each sump hole (middle 150mm)	2445	1800	
Depth of Water Table below Ground Level (m)	> 2.50		
Soil Percolation Values, Vp, s/mm	16.3	12.0	

Infiltration Testing

Infiltration tests were carried out in trial pits TP2 & TP4 in accordance with BRE Digest 365. The test results are tabulated below: -

Trial Pit No.	Pit Dimensions (W x L)m	Test Zone (mbegl)	In-Fill	Soil Infiltration Rate, f(m/s)
TP2	0.90 x 1.80	1.00 – 2.00		8.37 x 10 ⁻⁵
TP4	0.90 2.00	1.00-2.00	Open	2.77 x 10 ⁻⁴

GROUND ASSESSMENT

Published Geology

The British Geological Survey 1:50,000 Quaternary and Solid maps indicate that the site is overlain by Drumlithie Sand and Gravel Formation – sand and gravel. Sedimentary superficial deposits formed between 116 and 11.8 thousand years ago in the Quaternary Period. The site is underlain by Teith Sandstone Formation – sandstone. Sedimentary bedrock formed between 407.6 and 393.3 million years ago in the Devonian Period.

Encountered Ground Conditions

Made Ground and Topsoil: The majority of the site is overlain by made ground, 250-600mm in thickness consisting of reworked topsoils and compacted gravels. Topsoil was encountered beneath the made ground, 300-600mm in thickness to approximately 1.20m below ground level. Only TP4 was overlain by topsoil 350mm in thickness.

Natural Sub-Soils: The natural underlying sub-soils have an upper mantle of loose to medium dense red brown silty sand and gravel becoming medium dense red brown sand and gravel with rounded cobbles below 1.50m and proved to the maximum investigated depth of 2.50m.

Bedrock: Bedrock was not encountered during this investigation.

Groundwater Observations

No groundwater ingress was encountered during the investigation. There were no visual (no seepages or discoloration) indications of the seasonally high or fluctuating ground water table seen in the strata above 2.50m.

DISCUSSION

Sub-Soils

The sandy gravelly nature of the underlying sub-soils and the results from the percolation and infiltration testing confirmed the well to moderate draining properties of the sub-soils.

Sewage Treatment

The soil percolation values are in the range 12-16.3 s/mm and therefore it is required to provide secondary treatment prior to discharge.

A PSTP with a minimum 3,750-litre capacity is required for each 4-bedroom house with a population, PE = 6.

Foul Water Discharge

A sub-surface stone-filled soakaway (infiltration system) is considered suitable for the discharge of foul waters from a PSTP directly to the ground. The soakaway should comply with the Domestic Technical Handbook (para. 3.9.2) which sets out guidance on design in accordance with the requirements of SEPA Regulatory Method (WAT-RM-04) Indirect Sewage Discharges to Groundwater.

SuDS & Surface Water Disposal

The disposal of surface waters from the development needs to be assessed in terms of both the quantity and the quality of the discharge for Building Regulations and SEPA.

It is proposed to install a surface water infiltration trench for disposal to the ground. Using the SIA tool, the land use run-off quality has been determined, see following summary table: -

Land Use Type	Residential Roofing	Residential Parking & Driveway
Pollution Hazard Level	Very Low	Low
Pollution Hazard Indices		
TSS	0.2	0.5
Metals	0.2	0.4
Hydrocarbons	0.05	0.4
SuDS Component Proposed		
Component 1	None (not discharging to w	vatercourse)
Groundwater Protection Type		
	Infiltration Trench Additional Silt Traps for acc TSS - Minimum 300mm per	cess road and parking areas for rmeable gravel finish
Pollution Mitigation Indices		
TSS	0.4	0.4
Metals	0.4	0.4
Hydrocarbons	0.4	0.4
Combined Pollution Mitigation Indices		
TSS	0.4	0.4
Metals	0.4	0.4
Hydrocarbons	0.4	0.4
Acceptability of Pollution Mitigation		
TSS	Sufficient	Sufficient
Metals	Sufficient	Sufficient
Hydrocarbons	Sufficient	Sufficient

The SIA assessment confirms that the installation of infiltration trenches provides sufficient mitigation for the surface water run-off from the roof areas and access roads and permeable driveways/parking areas for the proposed development prior to disposal to the ground.

The designed and installed infiltrations are considered to be suitable for all weather conditions and not detrimental to the water environment and private water supplies.

DRAINAGE RECOMMENDATIONS

Foul Water Discharge

To comply with the Domestic Technical Handbook (para. 3.9.2) which sets out guidance on how proposals may meet the Building Standards set out in the Building (Scotland) Regulations 2004, an infiltration system must be designed and constructed in accordance with the requirements of SEPA.

Where the average soil percolation value, Vp is between 15-120 s/mm in accordance with the regulations the minimum base area, A, is derived from $A = Vp \times PE \times 0.25$, or a minimum base area of $25m^2$, see the following table: -

Proposed Development	Population Equivalent, PE (as defined in BW COP:18.11/14)	Min. Base Area (m²) Using a PSTP only
Each New Dwellinghouse	6 (4-bedroom)	25

Full details of the proposed sewage treatment system will be made available to the Building Standards Officer once it has been determined after consultation with suppliers which models are the most suitable for the proposed development and the potential population equivalent of the dwellinghouse.

SEPA

The final installed sewage treatment system and discharge will require to be registered with SEPA under CAR.

Surface Water Disposal

The sizes of the proposed surface water infiltration trench systems are based on the impermeable surface areas of the development i.e., the house roof, access road and driveways areas.

Using the lowest soil infiltration rate the calculated optimum dimensions for the surface water infiltration trenches are shown on the following table: -

Stone-Filled Infiltration Trench

Impermeable Areas (m²)	Length (m)	Width (m)	Storage depth (m)	Half Empty Time (hrs)
Each New Dwellinghouse & Garage Roof Areas up to 200m²	1.00 2.00 3.00 4.00	16.20 9.60 6.60 5.00	1.70	0.47 0.82 1.03 1.10

These dimensions are based on a 1 in 200-year storm event with +Climate Change Peak Rainfall Intensity Allowance of +39% for the Tay Region of Scotland and out in accordance with BRE Digest 365.

Proposed Drainage

The proposed drainage layout is shown on Fig 3. with indicative soakaway installation shown on Figs. 4 and 5 along with certificates all in Appendix A.

SYSTEM MAINTENANCE

Soakaways

The soakaways are designed for the life time of the proposed development if they are not allowed to silt up nor the pipework to be blocked.

If a soakaway fails to due blockages or silting it should be excavated and reconstructed with fresh clean stone, new pipework and renewed terram.

During the development of the site, and the excavation of the soakaways, should any field drains be found within 10m of the soakaway they should be realigned or relocated accordingly.

REGULATIONS

SEPA and Building Regulations require that infiltration systems (soakaways) are located at least:

- 50m from any spring, well or borehole used as drinking water supply
- 10m horizontally from any water course (including any inland or coastal waters), permeable drain (including culvert), road or railway
- 5m from all buildings
- 5m from boundaries (reduced distance to boundaries may also be subject to agreement from adjacent land owners where the soakaway is considered not to be detrimental to the adjacent property)

FOUNDATION RECOMMENDATIONS

Safe Bearing Capacity

It is recommended that the foundations should be taken down through the topsoil and any made or disturbed ground rest on the medium dense sands and gravels at a minimum depth of below 0.60m, allowing for frost cover, below existing ground levels.

A safe bearing capacity of 130kN/m² can be applied for foundation design.

Excavations

Due to the depth of the topsoil some excavation and replacement with suitable compacted upfill may be required to form the foundations.

Settlement

It is considered that the generally granular nature of the sub-soils will provide settlement within tolerable design limits.

De-Watering

It is not anticipated that de-watering of excavations will be required during construction.

APPENDIX A

Site Plans Fig. 1. General & Site Location Plans

Fig. 2. Test Location Plan

Trial Pit Logs TP 1-4

Drainage Fig. 3. Proposed Drainage Layout

Fig. 4. Indicative Foul Water Soakaway Construction

Fig. 5. Indicative Storm Cell Installation

Certificate Foul Water Discharges

Surface Water Disposal

Jun-23

Issue 1

Fig. 1. GENERAL & SITE LOCATION PLANS




Fig. 2. TEST LOCATION PLAN



GEDTECHNICAL	S ENVIRONALENTAL ONSITE SERVI	CLS	5.	A. MCG	REGOR	?	Site Mill of Kincardine, Fetter	cairn	Trial F Numb
racked exc	avator with	Dimens 0.90 x 2			Ground	Level (mOD)	Client Tulloch Farms		Job Numb 3386/
		Locatio	ocation		Dates 20	6/05/2023	Architect A.B Roger & Young		Sheet
Depth (m)	Sample / Tests	Water Depth (m)	Fie	ld Records	Level (mOD)	Depth (m) (Thickness		Description	Legend
.20-1.65	SPT(C) N=20		4,4/4,5,5,6 Percolation 1.50m			- (0.60) - (0.60) - (0.60) - (0.60) - (0.30) - (0.30)	MADE GROUND - rewo		ID and
			No ground	water ingress			Complete at 2.50m		
Plan .							Remarks		
							Scale (approx)	Logged By	Figure No.
							1:20	SAM	3386/23.TF

GEOTECHNICAL	8 ENVIRONGENIAL ONSITE SERVI	CES	S.A. MCGI	7EGO	?	Site Mill of Kincardine, Fettercairn	Trial Pi Numbe TP2
xcavation acked exc 90m buck	avator with	Dimens 0.90 x		Ground	I Level (mOD)	Client Tulloch Farms	Job Numbe 3386/2
		Locatio	n	Dates 20	6/05/2023	Architect A.B Roger & Young	Sheet 1/1
Depth (m)	Sample / Tests	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Description	Legend
					(0.30)	MADE GROUND - compacted gravels	
					0.30	TORON	
						TOPSOIL	
					(0.30)		
70-1.15	SPT(C) N=19		3,4/4,5,5,5		0.60	Medium dense red brown silty SAND and GRAVEL with occasional cobbles	
			Infiltration test zone 1.00-2.00		-		
			1.00-2.00		E		
					(1.40)		
					-		
					E	Less sitly more cobbly below 1.50m	
					-		
					F		
					-		
			No groundwater ingress		2.00	Complete at 2.00m	
					E		
					F		
					_		
					_		
					Ė		
					-		
					E		
					-		
lan .					<u>-</u> !	Remarks	
					s		gure No.
						1:20 SAM ad by the GEOtechnical DAtabase SYstem (GEODASY) © a	3386/23.TP


GEOTECHNICALS	CHVIRONIMENTAL ONSITE SERVI	318	S.A. MCGI	7EGOR	?	Site Mill of Kincardine, Fettercairn	Trial Pi Numbe TP3
racked exce	avator with	Dimens 0.90 x		Ground	Level (mOD)	Client Tulloch Farms	Job Numbe 3386/2
		Locatio	n	Dates 26	6/05/2023	Architect A.B Roger & Young	Sheet
Depth (m)	Sample / Tests	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Description	Legend
					(0.25)	MADE GROUND - compacted gravels	
					0.25	Loose red brown grey silty SAND and GRAVEL	
					(0.35)		
.60-1.05	SPT(C) N=20		5,5/5,5,5,5		0.60	Medium dense red brown SAND and GRAVEL	1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1
					-		
			Percolation testing at 1.00m				
					(1.40)	Less sandy and very cobbly below 1.20m	
					-		
					_		
					-		
			No groundwater ingress		2.00	Complete at 2.00m	
					-		
					_		
					-		
					-		
Plan					<u>E</u>	Remarks	
				•			
•				•			
•				•			
•				•			
•		٠		•			
•		•		•	s	cale (approx) Logged By	Figure No.
						1:20 SAM ad by the GEOtechnical DAtabase SYstem (GEODASY	3386/23.TP3


xcavation M racked excav 90m bucket	vator with	Dimens 0.90 x		Ground	Level (mOD)	Client	Job
Depth (m)		Locatio				Tulloch Farms	Number 3386/23
Depth (m)			on	Dates 26	6/05/2023	Architect A.B Roger & Young	Sheet 1/1
	Sample / Tests	Water Depth (m)	Field Records	Level (mOD)	Depth (m) (Thickness)	Description	Legend
						TOPSOIL	
60-1.05	SPT(C) N=21		4,5/4,6,5,6		- (0.60)	Medium dense dark orange brown very silty SAND and GRAVEL with some cobbles	
			Infiltration test zone 1.00-2.00m		- 0.95 	Medium dense red brown SAND and GRAVEL with many rounded cobbles	
					(1.05)	Becoming less sandy below 1.50m	
			No groundwater ingress		2.00	Complete at 2.00m	
					-		
Plan .						Remarks	
					<u> </u>	cale (approx) Logged By Fig	gure No.

Fig. 3. PROPOSED DRAINAGE LAYOUT



Fig. 4. INDICATIVE CONSTRUCTION (sketch only, not to scale)





CERTIFICATE FOR PROPOSED FOUL WATER SUB-SURFACE DISCHARGE

Two tests are normally required to demonstrate the suitability of the proposed drainage scheme:

1. A trial pit must be excavated to a depth of 1 metre below the proposed invert of the drain to establish whether the water table will interfere with the operation of the soakaway

and

2. A percolation test must be carried out to determine the area of the ground required.

Applicants: Tulloch Farm

Address: A.B Roger & Young Ltd

Site Address: Mill of Kincardine, Fettercairn, Laurencekirk, Aberdeenshire, AB30 1HA

Date of Test: 26th May 2023 **Time:** from 10am **Weather:** Dry and sunny

Encountered Ground Conditions

Made Ground and Topsoil: The majority of the site is overlain by made ground, 250-600mm in thickness consisting of reworked topsoils and compacted gravels. Topsoil was encountered beneath the made ground, 300-600mm in thickness to approximately 1.20m below ground level. Only TP4 was overlain by topsoil 350mm in thickness.

Natural Sub-Soils: The natural underlying sub-soils have an upper mantle of loose to medium dense red brown silty sand and gravel becoming medium dense red brown sand and gravel with rounded cobbles below 1.50m and proved to the maximum investigated depth of 2.50m.

Bedrock: Bedrock was not encountered during this investigation.

Groundwater Observations

No groundwater ingress was encountered during the investigation. There were no visual (no seepages or discoloration) indications of the seasonally high or fluctuating ground water table seen in the strata above 2.50m.

Wells: no known wells used for supply of potable water within 50m of site.

Percolation Tests

Development	TP1	ТР3	
Average time taken, seconds	2445	1800	
Soil Percolation Values, Vp, s/mm	>2.50		
Population Equivalent, PE	6 (All 4-l	pedroom)	
Minimum Soakaway Base Area m ²	2	5	

^{*} secondary treatment (PSTP) recommended

I hereby certify that I have carried out the above assessment in accordance with procedures specified within the Domestic Scottish Building Standards Technical Handbook (Environmental Standard 3.9 Infiltration Systems) and SEPA A WAT-RM-04, the results of which are tabulated above, and that the proposed drainage scheme detailed on the attached plans and report has been designed considering the recommendations in the standards and regulatory standards.

Signed

Date...21 June 2023

Name / Company Address

S. A. McGregor

Serenje, Kingsford Steadings, Alford, Aberdeenshire, AB33 8HN

Qualification B.Eng (Civil Engineering).

Jun-23

Issue 1

CERTIFICATE FOR PROPOSED SURFACE WATER DISPOSAL

Applicants: Tulloch Farm

Address: A.B Roger & Young Ltd

Site Address: Mill of Kincardine, Fettercairn, Laurencekirk, Aberdeenshire, AB30 1HA

Date of Test: 26th May 2023 **Time:** from 10am **Weather:** Dry and sunny

Encountered Ground Conditions

Made Ground and Topsoil: The majority of the site is overlain by made ground, 250-600mm in thickness consisting of reworked topsoils and compacted gravels. Topsoil was encountered beneath the made ground, 300-600mm in thickness to approximately 1.20m below ground level. Only TP4 was overlain by topsoil 350mm in thickness.

Natural Sub-Soils: The natural underlying sub-soils have an upper mantle of loose to medium dense red brown silty sand and gravel becoming medium dense red brown sand and gravel with rounded cobbles below 1.50m and proved to the maximum investigated depth of 2.50m.

Bedrock: Bedrock was not encountered during this investigation.

Groundwater Observations

No groundwater ingress was encountered during the investigation. There were no visual (no seepages or discoloration) indications of the seasonally high or fluctuating ground water table seen in the strata above 2.50m.

Wells: no known wells used for supply of potable water within 50m of site.

Infiltration Test	TP2	TP4
Infiltration Test Zone (m)	1.00-2.00	1.00-2.00
Soil Infiltration Rate, f (m/s)	8.37 x 10 ⁻⁵	2.77 x 10 ⁻⁴
Surface Area of Development	up to	200m²

Recommendation: -

Surface Water Infiltration Trenches

Plot 1 – $4m \times 5m$) each with 1.70m storage depth Plots 2 and 3 – $1m \times 16m$)

I hereby certify that I have carried out the above tests and calculations in accordance with BRE Digest 365 and in conjunction with the full requirements set out within the Domestic Scottish Building Standards Technical Handbook. The results of which are tabulated above, and that the proposed drainage scheme detailed within this report has been designed considering the recommendations in the standards.

Signed Date...21 June 2023 Name / Company S. A. McGregor

Address Serenje, Kingsford Steadings, Alford, Aberdeenshire, AB33 8HN

Qualification B.Eng (Civil Engineering).