


LDV55-EAO400AK

55" Outdoor Floor-standing Digital Signage



Features :

- Industrial design, waterproof SPCC housing, tempered protective glass.
- High brightness and anti-reflection glass ensure excellent visibility under direct sunlight.
- Dahua MPS platform provides unified remote management for system integrators and media operators.
- Strong 4 core processor provides powerful decoding capabilities, enabling premium display performance.
- Built-in media player software and USB player provide multiple methods to play contents.



Technical Specification

Display

Model	LDV55-EAO400AK
Backlight	LED
Screen Size	55"
Aspect Ratio	9:16
Resolution	2160×3840
Display Colors	16.7M
Brightness	2500nits
Contrast Ratio	1200:1
Viewing Angle(H×V)	178°/178°
Display Mode	Portrait
Response Time	8ms
Lifespan	50,000h

Connectivity

Input	RJ45 ×1, USB ×2, TF Slot ×1, HDMI ×1, Audio In×1
External Control	RJ45(LAN), USB
Wi-Fi	Optional
Speaker	5W×2
Smart Signage Platform	Media Publish System 3.0

Touch	Not Support
-------	-------------

Power & Environmental Conditions

Power Supply	AC110 or AC220V, 50/60Hz
Consumption	900W
Operating Temperature	-30 C ~+60 C (-22 F ~140 F)
Operating Humidity	5%~90%
Protection Level	IP65 customized
Cooling Method	Air conditioning(customized)

Mechanical Specification

Dimensions	2100x900x250mm (82.7"x35.4"x9.8")
Package	2350x1150x500mm (92.5"x45.3"x19.7")
Net Weight	178kg (392.4lb)
Gross Weight	203kg (447.5lb)

Internal Player

Processor	Quad-core Cortex-A17 up to 1.6GHz
Operating System	Android 8.1
RAM	2GB
Storage	16GB
Material Type	Video, audio, image, time, weather, countdown, txt, web page, stream media, pdf
Video	mp4,avi,mov,asf,wmv,rm,rmvb,mkv A single file can upload up to 2G, and the resolution cannot exceed 4K
Audio	mp3,wma,wav A single file can upload up to 500M
Image	jpg,jpeg,gif,bmp,png A single file can upload up to 30M, and the resolution cannot exceed 4K
Documents	pdf, doc, docx, ppt, pptx, xls, xlsx and txt. A single file can upload up to 200 MB
Decoding Capacity	1CH H265 4K@60/2CH H264 4K@25/2CH H265 1080P@30&2CH H264 1080P@25/4CH H265 1080P@30/2CH H264 1080P@25

Dimensions(mm)

