



Trulawn Edging

Plastic edging is 40mm x 40mm and available in 3m lengths.

Main Specifications					
Testing:	Standard DIN EN ISO	Result			
3 Point Bend	178	Flexural Stress	-5°C	MPa	21.2
		Bending E-Modulus			1,289
		Flexural Stress	23°C		11.6
		Bending E-Modulus			581
		Flexural Stress	65°C		4.6
		Bending E-Modulus			1.62
Tensile	527-2	Strength	MPa %	9.65	
		Tensile E-Modulus		659	
		Elongation		13.8	
Timed Tensile	899-1	Tensile E-Modulus	MPa	316	
		Tensile E-Modulus		202	
Timed 3 Pont Bend	899-2	Bending E-Modulus	MPa	380	
		Bending E-Modulus		271	
		Bending E-Modulus		235	
Pressure Characteristics	604	Compression Strength	MPa	1.8	
				2% Stretch	3.3
				10% Stretch	13.3
				20% Stretch	18.2
		Pressure E-Modulus		27.1	



Child Safe



Quick Draining



Pet Safe



UV Stabalised

