

Bird Nesting Boxes



Blue tit using a Standard bird box; not fully mortared in, allowing box front to be removed for cleaning and monitoring

These nesting boxes are suitable for many of the UK's small to medium size birds.

The Standard box


Our Standard nesting boxes are suitable for House Sparrows and members of the Tit family. The single entrance hole allows the entire internal area to be available for nesting and roosting. The aperture size will vary according to the target species (see [The Design](#)) and box fronts can be removable (4 stainless steel screws) if required.



Standard nest box, stretcher bond brick fronted

Sparrow terrace box

This has the same external dimensions as the standard box but has two entrance holes and two separate compartments – ideal for the sociable nature of house sparrows. The terrace box is also suitable for Redstarts, Black Redstarts and Wagtails.




Sparrow terrace box, stretcher bond brick fronted

Swift Box

This box has a crescent shaped hole to one side of the box, allowing swifts access but restricting use by starlings. Inside, a rough floor makes it easier for the birds to move around. The centre of the floor has a raised nest cup to assist the birds' nest building. The ideal internal depth of a swift box is 140 mm, however if cavity width is limited, boxes can be manufactured with a reduced depth (minimum 100 mm). Please specify requirements at the point of order.




Swift box, stretcher bond brick fronted



Swift box, internal

Starling box

This is the same as the standard box but with a 48 mm entrance hole. Like the swift nesting box, the ideal internal depth is 140 mm, however if cavity width is limited, boxes can be manufactured with a reduced depth (minimum 100 mm). Please specify requirements at the point of order.



Starling bird box, stretcher bond brick fronted.

All boxes can be supplied with bricks fitted in stretcher bond (half bond) and quarter bond (Flemish, English, both standard and garden wall bonds). Boxes can also be supplied without bricks for fitting into render walls and incorporating into stonework. The fronts have a stainless steel mesh to aid adhesion and are retained with stainless steel screws. All boxes have drainage holes.

T:01323 488732

enquiries@birdbrickhouses.co.uk

Bird Brick Houses Ltd. The Old Parlour,
Wilbees Farm, Arlington Nr Polegate
East Sussex BN26 6RU

Patented Product UK No: 1005180.3
Registration Community Design No's:
001319065-0001/0013190650002