


MTC Engineering (Cambridge) Ltd		Page 1
Ground Floor, 24 High Street Whittlesford Cams, CB22 4LT	Burwash Manor Greenfield Runoff rates	
Date 12/10/2023 04:38 PM File	Designed by JF Checked by	
Innovyze	Source Control 2020.1.3	

ICP SUDS Mean Annual Flood

Input

Return Period (years) 100 SAAR (mm) 552 Urban 0.000
Area (ha) 0.374 Soil 0.450 Region Number Region 5

Results 1/s

QBAR Rural 1.2
QBAR Urban 1.2

Q100 years 4.4

Q1 year 1.1
Q30 years 3.0
Q100 years 4.4