



The Barns, Linden Road, Clenchwarton
King's Lynn, Norfolk, PE34 4EL

Tel: (01553) 768335

Fax: (01553) 766172

E-mail: enquiries@dgmjoinery.co.uk

Website: www.dgmjoinery.co.uk

Facebook: www.facebook.com/dgmjoinery

Raynham Farm Company Ltd
Hall Farm
East Raynham
Fakenham
Norfolk
NR21 7EE

11th November 2023

F.A.O Octavia Raynham

Dear Octavia,

Window Specifications – Home Farm:

Please find specification of replacement windows installed at Home Farm, as our estimate number RFC/130223/GDG-01.

Sliding Sash Windows

- Spring Balanced Vertical Sliding Sash Window With Weatherseal & Trickle Ventilator.
- Brass Sash Lifts, Sash Stops & Locking Fitch Fasteners.
- Accoya High Performance Modified Timber.
- Traditional Internal Staff Beads.
- Traditional Ovolo Moulding To Sashes With 20mm Wide Ovolo Glazing Bars.
- 24mm (4-16-4) Clear Toughened Pilkington Optitherm S1 Plus Soft Coat, Argon Gas Filled Double Glazed Units With Warm Edge Spacer Bars.
- Factory Spray Finished With a 3 Coat Microporous Joinery Paint System – Colour Matched To Fenwick & Tilbrook No. 1 Snowdrop (White).

Casement Windows

- Side Hung Flush Casement Window With Weatherseal & Trickle Ventilator.
- Brass Butt Hinges, Casement Stays & Locking Casement Fasteners
- Accoya High Performance Modified Timber.
- Traditional Ovolo Moulding To Frames.
- Traditional Ovolo Moulding To Casements With 20mm Wide Ovolo Glazing Bars.
- 24mm (4-16-4) Clear Toughened Pilkington Optitherm S1 Plus Soft Coat, Argon Gas Filled Double Glazed Units With Warm Edge Spacer Bars.
- Factory Spray Finished With a 3 Coat Microporous Joinery Paint System – Colour Matched To Fenwick & Tilbrook No. 1 Snowdrop (White).

Yours Sincerely
For DGM Joinery Ltd

Gary Grange
(Project Manager)

