



NOTES

- 1) 6 no static galvanised steel circular columns installed into 225mm diameter sockets provided as part of court resurfacing works in 2015.
- 2) Column height 8m above existing ground level.
- 3) 8 no Philips BVP 65i lights fitted to new columns. 1 no fitting on columns M1, M3 M4 and M6, 2 no fittings on columns M2 and M5
- 4) Asymmetric beam setting used to minimise light overspill to adjacent properties.
- 5) New lights to be operated by token meters located on new service cabinet.
- 6) Isolation switch to be provided adjacent to existing meter in Clubhouse by Scottish Power to allow the new lighting to be connected.
- 7) New service cabinet containing distribution cabinet and individual court switching to be provided on Clubhouse wall.
- 8) New ducting provided to accommodate cabling between isolation switch and service cabinet.

KILMAURS TENNIS CLUB
 PROPOSED FLOODLIGHT INSTALLATION
 PLAN No 2 : SITE PLAN
 Scale 1 : 200
 Version 3
 October 2023