

NOTES

- 1) 6 no static galvanised steel circular columns installed into 225mm diameter sockets provided as part of court resurfacing works in 2015.
- 2) Column height 8m above existing ground level.
- 3) 8 no 450 watt DACA lights fitted to new columns. 1 no fitting on columns C1, C3, C4 and C6. 2 no fittings on columns C2 and C5.
- 4) Asymmetric beam setting used to prevent light overspill to adjacent properties. (See DIALux report dated 2<sup>nd</sup> June 2021 for more information).
- 5) New lights to be operated by token meters located on new service cabinet.
- 6) Isolation switch to be provided adjacent to existing meter in Clubhouse by Scottish Power to allow the new lighting to be connected.
- 7) New service cabinet containing distribution cabinet and individual court switching to be provided on Clubhouse wall.
- 8) New ducting provided to accommodate cabling between isolation switch and service cabinet.

