

# Cascade 115mm Deepstyle

Domestic Rainwater System



Combining period cast iron detailing and styling, Cascade 115mm Deepstyle is a semi-elliptical rainwater system providing greater drainage than the traditional half-round systems.

- Authentic detailing and finish on downpipe, guttering, hoppers and fittings
- Complements the Cascade soil system
- Incorporates 68mm round downpipe
- Choice of hopper styles with options to include a motif or date stamp
- Available in eight heritage colours

## Cascade 115mm Deepstyle Gutter Capacities

	Gutter Flow Capacity (Litres per second)		Maximum Roof (Area m <sup>2</sup> )	
	Level	1:600	Level	1:600
Outlet at one end	1.88	2.30	90	110
Outlet at centre	3.75	4.58	180	220

## Profiles

