



### TimeGuard

#### 4 Hour Electronic Boost Timer & Fused Spur

BoostMaster Fused Spur Countdown Switches now added to the range providing timed output protected by a BS1362 fuse switch.

Automatic timed countdown selections using simple push button programming with clear LED output status.

Simply replace existing single gang connection units or fixed appliance outlets.

Automatic timer countdown selection for up to 4 hours – 13A (3kW) loading.

Ideal for immersion heaters, room heaters, towel rails and lighting.

Replaces existing single gang connection unit or fixed appliance outlets. box min. 25mm deep.

Up to 5 on times can be selected: ¼ hour, ½ hour, 1, 2 and 4 hours.

- Setting Type - Digital.
- Contact Type - Normally open.
- Operating Voltage - 230V AC.
- Switch Rating 230V AC 13A (3kW) resistive, 1000W Filament lighting, 500W Fluorescent lighting 200W LED lighting, 100W CFL lighting.
- Easy push button selection with clear LED output status.
- Provides timed output protected by a BS1362 fuse switch.
- Timer Mode - Boost.
- Operating Temperature: 0 to 45°C.
- Wall Box - Minimum depth 25mm.
- EC Directives - Conforms to Latest Directives.
- Fits a standard flush or surface mount BS wall box min. 25mm deep.