



Quotation Ref Number: 230726092905	Date: 23/08/2023	Quote Validity: 30 Days
--	----------------------------	-----------------------------------

Customer Name: [REDACTED]	Customer Email: [REDACTED]	Customer Contact: [REDACTED]
Customer Address: Email Only	Delivery Address: YO19 6ES (Customer to confirm full address)	

Your Building Specifications:

Framing: Made from cold rolled Cee-section columns and rafters. All Purlins used are Top-hat sections . (Improved strength over zed purlins)	All framework is hot dipped galvanised steel to BS EN 10346:2009 Fe E390G-Z275 . The sections are designed to BS EN 1993-1-3:2006 using a combination of rational analysis and component testing.
Wall Detail: 24mm Box Profile Wall Cladding, Single Skin. Plastisol coated steel sheeting.	Colour: Juniper Green – BS No. 12B29 (Please see website for colour chart)
Roof Detail: 30mm Box Profile Roof Cladding, Single Skin. Plastisol coated steel sheeting. 30 degrees pitch with anti-condensation barrier and skylights.	Colour: Juniper Green – BS No. 12B29 (Please see website for colour chart)
Doors: 1x 2500mm x 2100mm Manually Operated Roller Door (Juniper Green) 1x 12 Point Locking Secure Personnel Access Door (Stock Grey) (Hinged on Right Side)	Windows: N/A
Rainwater Goods: Guttering & Downpipes - Galvanised Steel hot dipped in Plastisol coating, Juniper Green. All Base, Eaves & Ridge Fillers Included.	Fixings: All necessary screws (coloured cap-less finishing screws), bolt sets, masonry anchors, screw caps, brackets required to erect this building are supplied.

Your Building Dimensions:

Sizes: 3.6m x 8m x 2.5m to eaves with a 30 degrees pitch roof. Style of Building: Single Skin Building with 1x Roller Door & 1x PA Door
--



Erection Cost: £1,695.00 (Invoiced on Completion)	Supply Only: £8,610.00
Estimated Base Installation Cost: Please Call	All prices are exclusive of VAT.

Additional Information:

1) Quotation Includes Delivery
