



TOP HUNG IS SPLIT AND COUPLED ABOVE THE REVERSIBLE.

Item 1 : FRW Reversible




750 x 1510 : 1off
LANDING
WER Rating:'A' WER

Item 2 : Bevel Int Casement



1080 x 400 : 1off
BATHROOM P1
WER Rating:'A' WER

Item 3 : FRW Reversible



1080 x 1110 : 1off
BATHROOM P2
WER Rating:'A' WER

Bead type :Ovolo B62 28mm
 Colour :White
 Handle :White Casement Hdl
 Open in/out :Open out
 Glazed in/out :In
 Cill :150mm Standard
 Drainage :Base
 Add-on (Head) :20mm Frame Ext Cut
 Casement lock :TSL Espaq Roto (REV)
 Gearing :PN Gearing
 Viewed from :Outside
 Reinforcing rule :Standard
 Reinforcing type :RCM/Mixed
 FRW Block Dev :.
 FRW Brush Pile :Sash Only
 FRW Stop Block :.
 High Sec PAS24 :Not Included

Bead type :Ovolo B62 28mm
 Colour :White
 Handle :White Fab & Fix
 Friction stay :Standard Stav
 Glazed in/out :In
 Frame (Head) :60mm Standard
 Frame (Left jam) :60mm Standard
 Frame (Right ja) :60mm Standard
 Frame (Cill) :60mm Standard
 Cill :NO CILL
 Drainage :Face
 Add-on (Head) :20mm Frame Ext Cut
 Add-on (Cill) :H Coupler Cut to size
 Casement lock :TSL Espaq Roto
 Viewed from :Outside
 Reinforcing rule :Standard
 Reinforcing type :RCM/Mixed
 High Sec PAS24 :Not Included

Bead type :Ovolo B62 28mm
 Colour :White
 Handle :White Casement Hdl
 Open in/out :Open out
 Glazed in/out :In
 Cill :150mm Standard
 Drainage :Base
 Casement lock :TSL Espaq Roto (REV)
 Gearing :PN Gearing
 Viewed from :Outside
 Reinforcing rule :Standard
 Reinforcing type :RCM/Mixed
 FRW Block Dev :.
 FRW Brush Pile :Sash Only
 FRW Stop Block :.
 High Sec PAS24 :Not Included

- 1 x White : B78 20mm Add-On* @ 1080.00 : |-|
- 1 x White : B78 20mm Add-On* @ 750.00 : |-|
- 1 x White : SW754 Slim H Coupler @ 1080.00 : |-|
- 2 x CM150 End Caps for C150 (White)~