



- Ramp / landing Specification:** To comply with Approved Doc. M
- 1.5m wide ramp;
 - 5.8m long with a resin bond finish to both landing and ramp;
 - Metal tubular handrails with a brushed stainless steel finish; 950mm high above surface of ramp
 - Tubular posts, mid rail and 100mm kick plate sections; all with a brushed stainless steel finish;
 - 1.2m Wide (min.) clear width side steps with 55mm colour contrasting nosings to treads and riser;
 - Use textured pavings as going finish to 1st step only with slip resistance surface (Buff Colour)
 - 'Corduroy' hazard warning surface pavings to top & bottom of steps

No.	Date	Details
D	1-11-23	Changes to the surfacing of the ramp
C	18-10-23	Dims and text added to ramp & steps
B	12-10-23	Ramp & steps adjusted due to level difference
A	23-08-23	Changed to construction phase

CUSTOMER & CORPORATE SERVICES

Andy Ralphs
Strategic Project Team

Ballard House
West Hoe Road
Plymouth, PL1 3BJ
Tel: 01752 668000

Scheme
Midland House Decant
Location GF Ballard House

Drawing Title
External works - Proposed plan
Front section of East wing

Project Number 01977-20-03			
Drawing Number AL(90)04			
Date 01 11 23	Drawn CBD	Checked by	Date Checked
Scale 1:50			
Status Construction			
Revision D	O. D. S. A3		

THIS DRAWING IS COPYRIGHT ©