




Roof pitch



Interior finish options



White polyurethane
Maintenance-free and moisture resistant



White painted
Bright white finish for modern interiors

Glazing options

	Double glazing --70	Triple glazing --68	Triple glazing --66	Triple glazing --62
Rain noise reduction	✓	✓	✓	✓
Safety lamination	✓	✓	✓	✓
Toughened glass	✓	✓	✓	✓
UV filter	✓	✓	✓	✓
Easy-to-clean			✓	
Anti-dew			✓	✓
Thermal transmittance of glazing (U _g -value)	1.0	0.7	0.6	0.5

Read more about glazing specifications on p14.

Blinds and shutters

- Consider adding interior blinds for light-dimming or blackout and external blinds or shutters for heat protection.

Read more on p96.

Out-of-reach

- If your roof windows are going to be out-of-reach, consider our VELUX INTEGRA® electric and solar range on p32.

Energy efficiency

- For an energy efficient installation that's quick and easy, take a look at our full range of installation products on p80.

Manual centre-pivot

The original roof window GGL and GGU

The classic VELUX roof window is operated by a convenient top control bar that allows you to open and close the window even with furniture placed underneath it. It also features a ventilation bar so you can air out your room but keep the window closed.

- Convenient top opening
- Easy to rotate and clean the outer glass
- Integrated ventilation behind the control bar
- Ventilation filter protects against dust and insects



External frame sizes (w×h) cm	U _w -value	CK02	CK04	CK06	MK04	FK06	MK06	MK08	UK04	PK08	SK06	LEAD TIME	
	W/m² K	55×78	55×98	55×118	78×98	66×118	78×118	78×140	134×98	94×140	114×118	GB	NI
													days
White polyurethane													
GGU 0070	1.3	319	337	352	366	392	414	458	527	535	549	2	3
GGU 0068	1.1	409	427	442	456	482	504	548	617	625	639	2	3
GGU 0066	1.0	484	502	517	531	557	579	623	692	700	714	2	3
GGU 0062	0.92	569	587	602	616	642	664	708	-	785	799	8	9
GGU 0070Q	1.3	460	479	-	512	510	535	563	612	620	634	8	9
White painted													
GGL 2070	1.3	255	270	281	293	314	331	366	422	428	440	2	3
GGL 2068	1.1	345	360	371	383	404	421	456	512	518	530	2	3
GGL 2066	1.0	420	435	446	458	479	496	531	587	593	605	2	3
GGL 2062	0.92	505	520	531	543	564	581	616	-	678	690	8	9
GGL 2070Q*	1.3	340	409	-	378	412	416	451	507	513	525	8	9

* Special enhanced security window fitted with toughened laminated glass combined with a reinforced construction and extra locks.
Delivery time is approximate in working days from receipt of an order placed before 4pm (UK) and 11.30am (NI).

All prices in GBP (£)
Find all sizes and prices on velux.co.uk