

BLACK UPVC WINDOWS



Windows Do



Ultimate Double Glazing – our lowest U value

FUNCTION

Benefit	Low U Value
How it works	Outer pane reduces solar heat gain and provides high insulation, this combined with the Low E inner pane reflects heat back into the room.

PERFORMANCE

U-Value	1.22
G-Value	0.21
Window Energy Rating	E

Performance based on uPVC Casement with no bars.
A larger glass areas achieves the best U value, the addition of Georgian Bars will impact performance

COMPOSITION

Total Glazing Unit Size	28mm
Outer Pane	4mm Toughened SKNI76
Inner Pane	4mm PlaniTherm One
Gap Between Panes	20mm

GLAZING OPTIONS

Internal Georgian Bars	Optional
External Georgian Bars	Optional
Obscure Glass (Privacy)	Not available
Decorative Glass	Not available
Toughened	As standard
Leaded	Not available

COMPATIBILITY – WINDOWS

- EveryDay Storm
- Exclusives / Exclusives Premium Storm
- Exclusives Tilt & Turn
- Exclusives Upvc Sliding Sash
- Aluminium Casement

COMPATIBILITY – DOORS

- Exclusives/ Exclusives Premium Entrance Doors
- Aluminium Entrance and French Doors
- Aluminium Bi Fold and Sliding Patio Doors

