



Flush Fit Windows Rio

- 1 Same Eurogroove position as TOTAL70
- 2 28mm Glazing as standard with option for 34mm Triple Glazing
- 3 Detailed external chamfer for softer aesthetics
- 4 Three jointing options: Mechanical Joint, Fully Welded & Mech Weld
- 5 Exceeds weather performance standards as well as PAS24 accreditation
- 6 TOTAL70 frame detail
- 7 Optional deep bottom rail profile
- 8 Square edge bead for a contemporary aluminium look

Feature	Specification
Profile depth	70mm
Maximum sash size	1200 x 1200mm
Thermal performance	1.3 W/m ² K
Maximum sash weight	35kg (Fully Welded) 30kg (Mechanical Joint)
Glass Width	28mm & 34mm

