



Scope of Works

1. Strip out existing fence as required & remove all debris off site
2. Excavate front garden for proposed works removing debris off site
3. Provide square top precast concrete edgings flush with hard standing bedded in lean mix concrete to whole perimeter
4. Supply and lay min. 200mm deep sub-base of 20mm OGCR to whole area of proposed permeable paving.
5. Supply and lay min. 50mm thick laying course of 6mm washed aggregate.
6. Supply and lay Marshalls Driveline 50 Piora permeable block paving to form hard standing & ramp with perimeter border bedded in lean-mix concrete.
7. Permeable joints between blocks to be filled with washed aggregate
8. Construct vehicle crossing according to KCC Highways specifications.
9. Clear site & make good to surrounding area to match existing including grass seed as required



EXISTING AND PROPOSED ELEVATION

Revisions:

Client:
Mrs J Austen-Eves

Site:
Foord Road, Lenham

Project:
Vehicle Crossing & Parking

View:
Existing and Proposed Plans

Scale: 1:100@A3 Date: 08.23

Drawn by:
A Haggerty Drawing No:
93821/1



Home Improvement Agency
Suite 3, 2nd/ Floor | Fitted Rigging House
Anchor Wharf | The Historic Dockyard
Chatham | Kent | ME4 4TZ
08456 057017

**NOTE: DO NOT SCALE FOR CONSTRUCTION
CHECK ALL DIMENSIONS ON SITE**