



DOOR SCHEDULE		All doors, windows & ironmongery are to be AD M, AD K and DDA compliant.													
	Ref.	Room	Door Type	Structural Opening	Door Leaf Size	Swing	Specification	FR	Glazing	Finish	Frame	Architrave	Ironmongery Set Ref.	Lintel	
GROUND FLOOR	EXTERNAL DOOR														
	EXD01	Gym	1	1022.5x2100mm	To Suit Opeing		Smart Systems Ltd - Smart Wall Door Tel:01934 876100	N/A	28mm/ Lam Inner/ Tough outer	PPC Aluminium RAL colour TBC (To match existing)	PPC Aluminium	N/A	Push/pull handles, europrofile cylinder & HL Adams Rite MS2200 hook lock	TBC By S.E	

NOTE: All dimensions of existing openings are approximate & for estimating purposes only. All site dimensions should be checked prior to manufacture. \* = Obscure glazed