



Provision of Ramp/path:

Break out and excavate to reduced level as indicated on drawing to allow for construction of new ramp/path.

Ramp to be minimum width 1200mm.

Lay new platform and ramp using pre-cast concrete slabs at a gradient of 1:12 with 100mm pre-cast concrete upstands.

Include for an 'Aco' channel drain across ramp or as indicated connected to a soakaway uner lawn.

New Kee Clamp hand rails to sides of ramp/platform as indicated on drawing.

Make good to any areas disturbed around ramp/platform and remove all debris.

Provide new Pedestrian highway crossing to Rutland County Council specifications. Work to be carried out by an approved contractor only.

EXISTING

PROPOSED

Do NOT scale drawing except for planning purposes. All dimensions to be verified prior to work commencement. No decoration works have been included unless otherwise specified

		25 Sapphire Close Kettering Northants NN15 7DW Tel: 07545 589847	
Client	KEVIN CARTER	Address:	9 LAMMAS COTTAGE, COW LANE WHISSENDINE
Drwg. No:	CA1669/001	Rev:	Scale: 1:50
Date:	12/7/2023	Drawn by:	AB