



PATIO'S • DECKING • SHEDS

53 DENHAM DRIVE  
BASINGSTOKE  
HAMPSHIRE  
RG22 6IT

TELEPHONE: 01256 332256  
MOBILE: 07760 252588

03.10.2023

Mr Grellier  
Old School House  
Farleigh road  
Basingstoke  
RG25 2JL

Quotation no 9425  
Vat no;930300478

Work to be carried out.

- 1, Supply and erect 27 meters of 1200mm high pressure treated pointed palisade fencing and 2no gates
- 2, The posts for the fencing will be 1800mm x 100mm x 100mm pressure treated timber and will have a 75mm x 38mm mortice to allow the post to receive the rails
- 3, The arris rails will be pressure treated 3000mm x 75mm x 75mm
- 4, The palisades will be pressure treated 1200mm x 75mm x 22mm and pointed topped
- 5, All of the palisade will be fixed to the arris rails using 50mm galvanised nails
- 6, Both gates will be bespoke made pressure treated timber gates measuring at 1200mm(H) x 1200mm(W) ledge and brace
- 7, The gate fittings will be galvanised 450mm T Hinges ( 2 per gate ) and a medium auto catch ( 1 per gate )
- 8, All of the posts will be concreted into the ground at a depth of 600mm using a fast setting post mix

Total cost including 20% vat £1600.00

Please be advised due to timber being a natural product it may be prone to twisting or splitting.

Quotation is valid for Only 30 days.

CUSTOMER AGREEMENT.

I agree for the work to be undertaken for the price quoted.

Customer name.(please print).....

Customer Signature.....

