



T: 07943427445
E: info@infinitycooling.co.uk
W: www.airconditioningchelmsford.co.uk

Infinity Cooling Solutions
Great Notley
Braintree
Essex
CM77 7FP

Kathy Kershaw
The Old Bakery
15 North Street
Great Dunmow
CM6 1AZ

15th August 2023

Dear Kathy,

Please see below the details for the covers for the air conditioning units.

Specification: Cover 1 & 2 – 860mm wide x 900mm tall x 520mm deep. Cover 3 – 2000mm wide x 900mm tall x 520mm deep. Constructed with 45mm x 45mm timber corner posts and top framing, with slatted panels set between. Side and top panels to be fixed in position. Front panels to be removable for servicing access.

Panel style: 45/15 – Which denotes a slatted style panel with 45mm wide slats with 15mm gaps between slats. Material: Pressure treated, joinery quality softwood, planed all round.

Sound proofing: All covers will be lined with 10mm Celotex to dampen the units of the units.

Please do not hesitate to contact me if I can be of further assistance.

Kind regards.

Spencer Turner
Infinity Cooling Solutions
Director