



1050 x 2710mm (Daylight)

Sash & Case MK2 Cords & Weights

Viewed From Outside

Timber Type: Engineered Softwood

Splayed Glazing beads (as Main Timber Type)

4mm Clear Flt/4mm Softcoat 1.0 Flt (12)

4mm Clear Tgh/4mm Softcoat 1.0 Tgh (11)

16mm White Warm Edge Spacer

Argon filled

Brass Pulleys

Brass Non-Locking Brighton Fastener

Brass Ringlift

Brass Locking Ventlocks (x2)

27mm Bonded Astragal Bar with 18mm Inserted Spacer between glass
Frame 70/95 (+48-30 Head)

No vent

Supplied with 50mm diameter lead weights (supplied loose on pallets)
and supplied with sash cords.

Poly wrapped

White Weather strip (12)

Horn Type: Sash Stiles without Horns (12)