



# Appendix 1: Tree Survey Schedule

1	Norway Maple <i>Acer platanoides</i>	10	M	P: Good S: Fair - Historic basal wound on West side with associated decay. Prominent buttressing elsewhere	Overgrown canopy overhanging car parking bays  Reduce crown height - by 2.0m Reduce crown radial spread - by 2.0m Remove - Major dead wood	3 Months	24 months
18	Norway Maple <i>Acer platanoides</i>	14	M	P: Good S: Fair - Previously crown reduced. Squirrel damage in crown	Reduce crown height - by 2.5m Reduce crown radial spread - by 2.0m Remove - Major dead wood Raise low canopy - To 4.0m	3 Months	24 months
37	Common Ash <i>Fraxinus excelsior</i>	19	M	P: Fair S: Poor - Significant lower stem decay. Co dominant stems previously removed. Acute Easterly lean	Fell - Fell to safe height	3 Months	24 months



# Appendix 1: Tree Survey Schedule

50	Common Oak <i>Quercus robur</i>	10	M	P: Fair - Below normal vitality. Upper crown dieback S: Fair - Fungus at base with surface decay. Detached, degraded and difficult to ID but potentially Pholiota squarrosa	Zip line attached to stem at 3m.  Reduce tree to 4m high	3 Months	24 months
G57	Sycamore <i>Acer pseudoplatanus</i>	13	M	P: Good S: Fair - Squirrel damage in crowns	Northern boundary group  Trim back branches overhanging MUGA to clear. Remove stem marked with pink spot within group. This tree has suffered multiple branch breakages due to squirrel damage. Canopy overhangs MUGA	3 Months	24 months