

Tree Survey of Upper Quarry

Address of site:

Serious Stages
Tor Hill Works
Wells
BA5 3NT

Survey Conducted by:

Mr DRM Cole
ND Forestry & Arboriculture
QVT Inspector
LOLER Inspector
Cole.denis@sky.com
07989 333031

Date of survey:

06/09/2021
07/09/2021

Key:

Location = what3words
DBH = Depth at breast height
TRPD = Tree root protection, diameter of circle in metres

Inspection Revealed no root protection areas.

Tree No	Location	Species	DBH approx	Condition	Recommendation	TRPD
1	Habbits Alpha Puzzes	Ash, Fraxinus Excelsior	30cm	90% die back	Over Right of Way. Remove	
2	Habbits Alpha Puzzes	Ash, Fraxinus Excelsior	30cm	90% die back	Over Pedestrian Access. Remove	
3	Habbits Alpha Puzzes	Hawthorn, Crataegus Monogyna	15cm	Good	No Action	1.8
4	Unicorn Groves Shame	Hazel, Corylus Avellana	5-12cm	Multistem. Good	No Action	1.5
5	Unicorn Groves Shame	Oak, Quercus Robur	34cm	Heavy Lean. Good	Over Public Access. No Action	4.08
6	Unicorn Groves Shame	Hawthorn, Crataegus Monogyna	4-10cm	Multistem. Good	Over Public Access. No Action	3.5
7	Unicorn Groves Shame	Oak, Quercus Robur	40cm	Good	Severe Ivy	4.8
8	Given Waffle Blush	Sycamore, Acer Pseudoplatanus	34cm	Good	No Action	4.08
9	Excellent Status Gravitare	Oak, Quercus Robur	60cm	Canopy Good. Minor Deadwood	Remove soil back to root crown	7.2
10	Excellent Status Gravitare	Oak, Quercus Robur	45cm	Canopy Good	Remove soil back to root crown	5.4
11	Argued Taps State	Oak, Quercus Robur	42cm	Good	Lower Limbs removed incorrectly. Prune to rebalance canopy	5.04
12	Poetic Tribal Brew	Hazel, Corylus Avellana	4-12cm	Good	Correct Poor cuts	2.5
13	Poetic Tribal Brew	Hazel, Corylus Avellana	4-14cm	Multistem. Good	Reduce extensive end weight	2.4
14	Poetic Tribal Brew	Hawthorn, Crataegus Monogyna	6-10cm	Good	No Action	2.4
15	Rips sheilding Because	Hawthorn, Crataegus Monogyna	12-8cm	Good	No Action	2
16	Rips sheilding Because	Hazel, Corylus Avellana	10-18cm	Good	No Action	2
17	Rips sheilding Because	Oak, Quercus Robur	50cm	Reasonable. Showing signs of stress. Large angle of lean and excessive end weight	Reduce end weight to balance	6
18	Scanty Stress Bakers	Hazel, Corylus Avellana	4-15cm	Root crown exposed and evident ground heave	Remove, direction of failure over public access	
19	Scanty Stress Bakers	Hazel, Corylus Avellana	4-15cm	Root crown exposed and evident ground heave	Remove, direction of failure over public access	
20	Scanty Stress Bakers	Hazel, Corylus Avellana	4-15cm	Root crown exposed and evident ground heave	Remove, direction of failure over public access	
21	Clays When Earful	Field Maple, Acer Campestre	30cm	Good. Some root exposure	No Action	3.6
22	Clays When Earful	Field Maple, Acer Campestre	32cm	Good. Some root exposure	No Action	3.84
23	Clays When Earful	Field Maple, Acer Campestre	38cm	Good. Some root exposure	No Action	4.56
24	Career Refer Gap	Beech, Fagus Sylvatica	60cm	Good	No Action	7.2
25	Career Refer Gap	Oak, Quercus Robur	16cm	Good	No Action	1.92
26	Career Refer Gap	Oak, Quercus Robur	54cm	Good	No Action	6.48
27	Career Refer Gap	Hazel, Corylus Avellana	4-10cm	Good	1 Leader failed over public right of way. Remove	
28	Inovator Starring Mutual	Ash, Fraxinus Excelsior	20cm	Good	Over public right of way. Remove	
29	Inovator Starring Mutual	Ash, Fraxinus Excelsior	15cm	95% die back	Over public right of way. Remove	
30	Inovator Starring Mutual	Ash, Fraxinus Excelsior	10cm	90% die back	Over public right of way. Remove	
31	Inovator Starring Mutual	Ash, Fraxinus Excelsior	10cm	Reasonable	No Action	1.2
32	Inovator Starring Mutual	Ash, Fraxinus Excelsior	15cm	Reasonable	No Action	1.8
33	Inovator Starring Mutual	Ash, Fraxinus Excelsior	20cm	Reasonable	No Action	2.4
34	Inovator Starring Mutual	Ash, Fraxinus Excelsior	20cm	Cambium die back at base	Remove 2 large dead limbs	2.4
35	Inovator Starring Mutual	Holm Oak, Quercus Ilex	50cm	Good	No Action	6
36	Talent Snowballs Casual	Field Maple, Acer Campestre	25cm	Good	No Action	3
37	Transit Squaking? Sprain	Sycamore, Acer Pseudoplatanus	18cm	Good	No Action	2.16
38	Transit Squaking? Sprain	Ash, Fraxinus Excelsior	23cm	Reasonable	No Action	2.76
39	Transit Squaking? Sprain	Sycamore, Acer Pseudoplatanus	50cm	Reasonable. 2 minor cavities at 4m	Severe Ivy	6
40	Pulse Certified Headless	Wild Cherry, Prunus Avium	28cm	Dead standing	Adjacent to public right of way. Remove	
41	Pulse Certified Headless	Ash, Fraxinus Excelsior	38cm	Reasonable	No Action	4.56
42	Pulse Certified Headless	Ash, Fraxinus Excelsior	20cm	Small leaves showing signs of stress	Review	
43	Pulse Certified Headless	Sycamore, Acer Pseudoplatanus	40cm	Reasonable	No Action	4.8
44	Extremely Tonsils Melt	Ash, Fraxinus Excelsior	25cm	90% die back	Remove	
45	Extremely Tonsils Melt	Ash, Fraxinus Excelsior	25cm	85% die back	Remove	
46	Extremely Tonsils Melt	Ash, Fraxinus Excelsior	20cm	30% die back	Remove	
47	Extremely Tonsils Melt	Ash, Fraxinus Excelsior	25cm	40% die back	Remove	
48	Extremely Tonsils Melt	Ash, Fraxinus Excelsior	20cm	90% die back	Remove	
49	Extremely Tonsils Melt	Ash, Fraxinus Excelsior	15cm	co-dominant limb failue at base. 30% die back	Remove	
50	Extremely Tonsils Melt	Field Maple, Acer Campestre	12cm x2 Codominant	Good	No Action	2.88
51	Extremely Tonsils Melt	Ash, Fraxinus Excelsior	15cm	Dead standing	Remove over road	
52	History Guidebook Sorehand	Oak, Quercus Robur	90cm	Good	No Action	10.8
53	Striped Towel Food	Holm Oak, Quercus Ilex	18cm	Good	No Action	2.16
54	Striped Towel Food	Holm Oak, Quercus Ilex	10cm	Good	No Action	1.2
55	Striped Towel Food	Holm Oak, Quercus Ilex	25cm	Good	No Action	3
56	Striped Towel Food	Holm Oak, Quercus Ilex	25cm	Good	No Action	3

57	Striped Towel Food	Oak, Quercus Robur	15cm	Good	No Action	1.8
58	Striped Towel Food	Holm Oak, Quercus Ilex	25cm	Codominant good	No Action	3
59	Striped Towel Food	Beech, Fagus Sylvatica	30cm	Good. Triple central Leader	No Action	3.6
60	Striped Towel Food	Beech, Fagus Sylvatica	20cm	Codominant good, large fisher but reaction growth good	No Action	2.4