

SIDE SECTION

**125mm gutterring
clipped every 800mm**

**8x2 timber joists
felled and roof tiles with lead flashing**

**ceiling to be insulated with 100mm insulation
and then 12mm plasterboard and plastered**

steel lintels to be used over external windows and doors

Walls to be built out of H+H aerated concrete block with cavity insulation

**floor
150mm hardcore with 1200 gauge visqueen, 120mm celotex insulation with 100mm concrete slab
and self levelling compound on top**

**foundations
600mm x 300mm thick concrete foundations.
2 course of block down below DPC**

