

HIGH EFFICIENCY LED SLIMLINE FLOODLIGHTS

MEAN WELL DRIVER | PC COOLER HEAT SINK | 5 YEAR WARRANTY

APPLICATIONS

- Building facades illumination
- Area Floodlighting
- Industrial Premises
- Small sports ground
- Perimeter & Security lighting
- Amenity

SPECIFICATION

- Efficacy (Lm/W): 115
- Voltage (V AC): 100-240V
- Frequency (Hz) :50/60
- Power factor : >0.9
- Rated Switch Cycles: 40,000
- Beam Angle (°): 120
- Colour temperature (K): 6000
- Flicker free Meanwell driver
- Colour rendering index (CRI): 80
- Surge Protection (kv): 6
- Operating temperature (°C): -20 / +45
- Average lifetime (hrs): 30,000
- IP / IK Level: 65/08
- Output Voltage (DC): 30V
- Electrical Safety Class 1



CONSTRUCTION

- Anti Corrosive & Slim Design
- IP65 cable gland
- IP65 black housing
- Tempered Glass
- Polished Aluminium Reflector



SKU CODE	DESCRIPTION	WATTS	LM	INPUT CURRENT (MA)	OUTPUT CURRENT (MA)	WEIGHT (KGS)	SIZE (LXWXH)
FL-SMD-80W-6000K-B	80W LED SMD Flood Light - Mean Well Driver	80	9200	350	2360	2.8	245x354x55mm
FL-SMD-100W-6000K-B	100W LED SMD Flood Light - Mean Well Driver	100	11500	435	2960	3.75	295x420x60mm
FL-SMD-150W-6000K-B	150W LED SMD Flood Light - Mean Well Driver	150	17250	653	4440	4.75	330x430x60mm
FL-SMD-200W-6000K-B	200W LED SMD Flood Light - Mean Well Driver	200	23000	870	5920	5.85	360x470x60mm

