

•	Proposed Buildings	:	2195.25 m²
•	Permeable Parking Areas	:	468.75 m²
•	Impermeable Access Road & Driveway	:	1790.00 m²
•	Impermeable Footpath	:	57.00 m²
•	Total Hardstanding Area	:	2315.75 m²
Accord	ding to the ground investigation report	the ground	condition is typically ur

Drainage merarchy						
Drainage Hierarchy	Y/N	Comment				
1. Infiltration to maximum extent	Ν	Ground Condition is not suitable for Soakaway System				
2. Discharge to Surface Waters	Ν	None Available				
3. Discharge to Surface Water Sewer	Y	Discharge into Existing Private Storm Water Manhole an				
		then discharge into Anglian Water Sewer System				
4. Discharge to Combined Sewer	Ν	None available				

UNLESS STATED WITHIN THE CONTRACT THESE DRAWINGS ARE COPYRIGHT AND THE PROPERTY OF PARSONS CONSULTING ENGINEERS LTD. COPYING OF THE DESIGNS, DRAWINGS OR INTELLECTUAL PROPERTY IN FULL OR IN PART IS NOT PERMITTED.

### Notes

- Do not scale this drawing, other than for Planning Application purposes.
- 2. All dimensions are in millimetres unless stated otherwise.
- This drawing to be read in conjunction with all other relevant drawings and specifications.
- All proprietary items to be installed in strict compliance with manufacturers instructions and recommendations.

STANDARD DRAINAGE NOTES:

- 1. Except where specifically shown otherwise all below ground pipes / connections shall be 100mm dia PVC (to BS 4660) or VC (to BS 5481) with flexible joints and laid to minimum falls of 1 in 40, except where connected to WC when falls may be 1 in 80.
- 2. All gravity pipe runs to be tested to a standing head of 1500mm head of water above the invert at the head of the pipe run (but not exceeding 4000mm at the lower end)
- 3. For details of bed and surround requirements refer to long-sections and standard details. In all other situations provide 150mm of 10mm single-sized rounded gravel bedding and surround.
- 4. Except where specifically shown otherwise, pipes to be a minimum of 900mm below roads/driveways and 600mm below gardens/fields
- 5. Ventilating pipes to be provided at the head of each drain and to any branch longer than 6m where a single appliance is connected, or 12m where a group of appliances is connected
- 6. Step-irons shall not be fitted in any chambers unless specified otherwise.
- 7. Manhole/Gully covers shall be regulated to suit finished levels and crossfalls
- 8. All proprietary items to be installed in strict compliance with manufacturers instructions and recommendations
- 9. Drains passing beneath buildings to have minimum 100mm granular fill or flexible filling around pipe. Where the pipe crown is within 300mm of the underside of the slab, pipe shall be encased in concrete integral with the slab.
- 10. Drains passing through walls below ground level to have minimum 50mm clearance all round and opening in walls to be masked all round with rigid sheet material to prevent ingress of fill or vermin. Openings in walls for pipes shall have concrete lintels to support wall construction above
- 11. Unless stated otherwise, pipes to be 150mm Diameter. 12. Unless Stated otherwise car parking spaces subbase to be 350mm type 3 granular material

STANDARD ROADS / FOOTPATH NOTES:

- 1. Existing structures to be broken out to minimum 450mm below top of finished surface level. Existing footpath to be broken out and rubble and existing subbase to be removed off-site.
- 2. Subgrade to be proof rolled with one pass of a smooth-wheeled roller having a mass per M-width of roll of not less than 2,100-kg or a Vibrating Roller having a mass per M-width of roll of not less than 700-kg or a Vibrating Plate Compactor having a mass per m2 of not less than 1400-kg. Any soft spots shall be removed and replaced with
- Type 1 compacted in layers not exceeding 150mm thickness. 3. All formations are to be treated with an approved herbicide before placing sib-base material on a geotextile separation
- membrane (Terram 1000 or similar approved) 4. All sub-base material is to be non-frost-susceptible. All concrete to be sulphate resisting

P02	Updated Site Layout Plan & Amended Drainage Design	EP	04-09-23
P01	Planning Issue	EP	07-08-23

Mr Andrew Wright

Client

## Project Piperell Way, Haverhill

# Drainage Strategy Plan Option 2

Job No	22111			
Drawing No	° 22111-004			P02
Status	Planning			Rev
Scale	1:250@A1	Date 07-08-2023		
Project	ТВР	Drawn	Ву	EP
Ligilleei		Checke	ed By	AJP
		Approv	ved By	



4 Angel House, Eastgate, Whittlesey Peterborough, PE7 1SE 07961 783825

www.parsonsengineers.co.uk