

Heritage Statement

PLANNING APPLICATION FOR THE DEMOLITION OF AN EXISTING GARAGE AND ITS REPLACEMENT

Kent House

East Harting, GU31 5LS

Prepared by: Palmer Heritage Ltd

Client: Edward and Victoria Bonham Carter

January 2023

Contents

1.	Introduction	1
2.	HERITAGE POLICY CONTEXT	2
	National Policy.....	2
	Planning (Listed Buildings and Conservation Areas) Act 1990	2
	Revised National Planning Policy Framework 2021.....	2
	National Planning Policy Guidance 2019	3
	Definition of ‘curtilage listing’	3
	South Downs National Park Authority Policy.....	3
	South Downs Local Plan 2014-2033	3
3.	HISTORIC DEVELOPMENT.....	5
4.	DESCRIPTION AND SIGNIFICANCE OF THE SITE	9
	Listed Building Description.....	9
	External Description of Kent House and its Setting.....	10
	Heritage Value of the Assets	12
5.	IMPACT ASSESSMENT AND JUSTIFICATION	14
	Extent of the works	14
	Design Justification and Impact Assessment	14
	Conclusions	15
	APPENDIX 1: HISTORIC MAPPING	16

1. Introduction

- 1.1 This Heritage Statement has been prepared to support planning applications in relation to the demolition and replacement of a garage at Kent House, East Harting, and the associated re-location of a domestic oil tank. The proposed development site is part of the setting of a Grade II listed building located in the Chichester District Council area and is within the South Downs National Park.
- 1.2 This document will set out the policy context, describe the history and significance of the site, assess the impacts of the proposed works on the listed building, and provide a justification for the proposed works.
- 1.3 The document is intended to be read alongside the drawings and Design and Access Statement prepared by Pelican Architecture and Design Ltd, and the Planning Statement prepared by Planit Consulting Ltd.

2. HERITAGE POLICY CONTEXT

National Policy

Planning (Listed Buildings and Conservation Areas) Act 1990

- 2.1 Section 66 of the Act establishes a general duty for a planning authority, in considering whether to grant consent for a development which affects a listed building, to have special regard to the desirability of preserving a listed building or its setting or any features of special architectural or historical interest which it possesses. A building is listed by virtue of its special architectural or historical interest (Section 1(1)).

Revised National Planning Policy Framework 2021

- 2.2 The revised National Planning Policy Framework (NPPF) was published in July 2021. Section 16 of the NPPF deals with the consideration of heritage assets and sets out the importance of being able to assess the impact of a development on the significance of heritage assets. Significance is defined as the value of an asset because of its heritage interest. The setting of an asset can contribute to this interest. The setting of a heritage asset is defined as the surroundings in which a heritage asset is experienced. Its extent is not fixed and may change as the asset and its surroundings evolve. A designated heritage asset is recognised by the NPPF to be a World Heritage Site, Scheduled Monument, Listed Building, Protected Wreck Site, Registered Park and Garden, Registered Battlefield or Conservation Area designated under the relevant legislation; of these, World Heritage Sites, Scheduled Monuments, Grade I and II* Listed Buildings and Parks and Gardens, Protected Wreck Sites and Registered Battle Fields are noted in paragraph 200 as being of the 'highest significance'.
- 2.3 The NPPF recognises that a balance needs to be struck between the preservation of the significance of a heritage asset and delivering public benefit. With regard to designated assets, paragraph 199 states that the more important the asset, the greater the weight should be on its conservation. Distinction is drawn between those assets of highest significance and those of a lesser significance.
- 2.4 The NPPF identifies harm as being either substantial or less than substantial. Paragraph 201 states that where the proposal would lead to substantial harm to the significance of a designated asset consent should be refused unless the harm or loss is necessary to achieve substantial public benefit that outweighs that harm. In cases where less than substantial harm to the significance of a designated asset is anticipated, paragraph 202 requires that this harm should be weighed against the public

benefits of the proposal. In respect of non-designated assets, paragraph 203 requires a balanced judgement having regard to the scale of any harm or loss and the significance of the asset.

2.5 In accordance with the NPPF, this Heritage Impact Assessment sets out the significance of heritage assets likely to be affected by the proposed works. The information provided in this assessment conforms to paragraph 194 of the NPPF, thus the level of detail provided is proportionate to the significance of the affected heritage assets and no more than is sufficient to understand the potential impact of the proposal on that significance.

2.6 Guidance on the application of heritage policy within the NPPF is provided within the Historic England 'Good Practice Guides' and the on-line National Planning Policy Guidance (NPPG) for the Historic Environment.

National Planning Policy Guidance 2019

2.7 The NPPG provides guidance as to the application of policy as regards heritage assets and defines the qualities of a listed building and conservation area, including reference to curtilage structures or features.

Definition of 'curtilage listing'

2.8 The Planning (Listed Buildings and Conservation Areas) Act 1990 states that "any object or structure within the curtilage of the [listed] building which, although not fixed to the building, forms part of the land and has done so since before 1st July 1948 shall be treated as part of the [listed] building". Within the Town and Country Planning Act 1990, a structure is defined as within the curtilage if "incidental to the enjoyment of the dwelling-house"; this has been further legally interpreted as ancillary to the main building.

South Downs National Park Authority Policy

2.9 Though Kent House is located in the local authority area of Chichester, the Chichester Local Plan does not cover the area of the South Downs National Park, which instead falls under the remit of the South Downs National Park Authority. Therefore, the local policy relevant to this application is that of the National Park.

South Downs Local Plan 2014-2033

2.10 The South Downs Local Plan was adopted in July 2019.

- 2.11 Chapter 4 of the Local Plan sets out the key objectives, and policy SD1, at point 2, sets out the aspiration to 'conserve and enhance the cultural heritage of the area'. Point 4 states that planning permission will be refused if the proposed development fails to adhere to this objective, unless the development can clearly benefit over-riding benefits, or substantially complies with other relevant policies.
- 2.12 Chapter 5, 'A living, thriving landscape', contains policies specifically relating to heritage. Those relevant to this application are SD12 (Historic Environment) and SD13 (Listed Buildings). SD12 seeks to ensure developments conserve and enhance the historic environment, and notes that Heritage Statements are required to set out the significance (value) of assets and the potential for harm to these assets. The policy is broadly in line with that set out in the NPPF.
- 2.13 Policy SD13 uses the wording 'preserve and enhance' in relation to listed buildings, and states the need for it to be demonstrated during development that loss of materials and features have been avoided, including internal elements such as floor plans and the integrity of rooms.

3. HISTORIC DEVELOPMENT

- 3.1 Early historic mapping can be found at Appendix 1. Kent House is located in East Harting, to the west of the village on Kent House Lane.
- 3.2 Harting is mentioned as the Manor of 'Hartinge' in the Domesday Book in 1086. A deerpark, part of the Manor of Harting, was owned from before 1274 by Henry Hussee and described as a 'park at Harting on the hills'. This was mentioned in documents by 1370 as 'Uppemark', and included much of the land including and around East Harting. The Manor was passed between the crown and various noble families until its purchase in 1746 by Sir Matthew Fetherstonhaugh¹. However, the Sussex Estate Maps of 1750 show that Kent Farm (as Kent House was previously known) was at that time in the possession of Mr Richard Luff². Adjacent lands are shown to be owned by 'Miss Fetherstonhaugh'.
- 3.3 The maps of 1750 (Appendix 1, Map 1) are charmingly drawn, and Kent Farm is depicted as a house with a central chimney and four windows across. To the north of the house is a barn, and a carthouse is drawn to shown open timber framed sides. 'The Garden' is to the south of the house. The land is described as encompassing around 25 acres, including 'Kent Meadow' or 'The First Meadow' to the south, and two acres to the east of the house 'part arable and part meadow'. To the west, across what was then called 'The Lane' a plot is indicated where there are currently barns (now converted); however, no building or ownership details are shown.
- 3.4 The drawings on this map indicate that buildings at Kent Farm had existed on the site prior to 1750, and also that some change in their appearance took place in the 18th century. Certainly the drawing on the maps does not align with the appearance of Kent House as it stands today; it is possible that the earlier house was built as part of the estate building of Uppark in the late 17th century, and remodelled in the 18th century by new owners. Whilst this is supposition it would make some sense that re-fronting and re-roofing happened as the farm became separate to the Uppark estate. As it is, the house dates from the 18th century in appearance.

¹ A history of the Medieval ownership and development of the Manor of Harting and estate of Uppark is given in 'Harting', in A History of the County of Sussex: Volume 4, the Rape of Chichester, ed. L F Salzman (London, 1953), pp. 10-21. British History Online <http://www.british-history.ac.uk/vch/sussex/vol4/pp10-21>

² Sussex Estate Maps: 'A Plan of Estates belonging to Mr Richard Luff in 5 sheets', 1750 (photographed in 1956 by permission of Sir H Meade Fetherstonhaugh). Accessed at West Sussex Record Office, Chichester.

- 3.5 Estate plans of 1785 (Appendix 1, Map 2), again taken from a manuscript related to the Uppark Estate, show the buildings to the east side of the lane, and the fields known as the Allan Field and the Well Field to the east of the lane, with 'Mrs Patrick's Lands' to the north.
- 3.6 The title maps of 1840 (Appendix 1 Map 3) show that the ownership of Kent Farm had changed again; the farm was owned by William Poore and occupied by Joseph Postlethwaite. The principle packages were 345 and 346, occupied by the farm buildings and to either side of the lane; in addition, the farm encompassed 352, the field to the south, and 352a, the plantation running west of the farm. Kent Allan field to the north, and other adjacent land, was owned by Sir Henry Fetherstonhaugh of Uppark, and were part of the Uppark estate. The Well Field, 358, was owned by William Poore, owner of Kent House; it was in use by James Lever, though noted to be part of Kent Farm. The buildings marked are broadly in place where they are today, though the rear (north) portion of Kent House appears to have a slightly different shape with a central rear wing rather than to the west side of the rear. What may previously have been the carthouse shown on the 1750 plans, to the east of the house, and the barn to the north, are in place, and are both coloured black indicating that they are uninhabited buildings as opposed to Kent House which is coloured red to show habitation. At some point before the 1861 census the ownership of the farm passed to Joseph Postlethwaite, and by 1867³ he is residing at North End and John Lever (son of James Lever mentioned in 1840?) is resident at Kent House.
- 3.7 By 1875 (Appendix 1, Map 4) Kent Farm was shown on Ordnance Survey (OS) mapping as Kent House, and the labelling to the east of the lane suggests that the barns to this side were still part of the farm landholdings in the 19th century. The building plots correspond to that seen on the site today; the rear portion of Kent House is shown to the west side of the rear, and enclosed gardens are shown to the west of the house, with a small ancillary building or shed to the northern end of the garden. The plantation and fields to the south were used by John Lever throughout the late 19th century and he occupied Kent House during that time according to census records; OS mapping of 1898 (Appendix 1, Map 5) shows no change to the land or buildings from 1875, except that the field to the south, previously having had a fence line running east to west across separating Kent Meadow from the Well Field, is now shown open all the way to the road on its southern boundary.
- 3.8 By the time of the 1901 census, Kent House had been sold to Kenhelm Chandler, a retired railway station manager who lived there with his wife and family. His son helped on the farm, and they had a servant. The 1911 census noted that the property comprised nine rooms, which broadly correlates

³ Kelly's Post Office Directory (Essex, Herts, Middlesex, Kent, Surrey and Sussex), 1867

with the number of rooms the house has today when the attic is included. OS mapping of 1912 (Appendix 1, Map 6) shows Kent House much the same as in 1898. However, changes to the gardens and outbuildings took place between 1912, and the next available clear mapping of 1962. In 1912, the walled garden to the north-west of the house was not yet in its current form, with a garden boundary being present in a different place and running east-west, to the south of the line of the plantation. In the area of the current garage a smaller building is shown slightly to the south in the earlier mapping. By 1946, as shown in a historic aerial photograph from that year (Appendix 1, Map 7), both the southern boundary of the walled garden and a garage building on the site of the present garage had been constructed, though the garage was replaced in the 1990s. The potting shed within the walled garden appears to date from the mid-20th century, though a building in this area has been on mapping since the 19th century as noted above. It is difficult to see clearly from the photograph the form of the garden at this time, but it appears that there were some trees to the southern and northern boundaries of the walled garden. An aerial photograph of 1973 (Appendix 1 Map 8) shows a number of trees on the site, including around the northern and southern boundaries of the walled garden, and to the east of the house around the shed and parking area, as well as those which had historically formed the plantation to the west of the house. This photograph shows a simple but formal flower-bed layout within the square walled area, but no garden buildings are visible; this is probably due to tree cover as it is known that at least a garden shed in some form had been in place for many years.

- 3.9 The OS map of 1971 (Appendix 1 Map 9) shows all these changes, with the site appearing much as it does today; in addition, this map shows the first instance of Kent Cottage and Cole Cottage, the former barn located to the north of the house, having separate name labels. Therefore it is probable that at some point during the earlier part of the 20th century, either under the ownership of Kenhelm Chandler or slightly later that of the Moens family, the formation of the walled garden as it currently stands and the conversion of the barn to cottages took place. It is notable that there are no census records prior to the late-20th century that indicate any habitation of the cottages. The Moens family owned Kent House and its associated land from 1937 onwards, until its sale in 2022.
- 3.10 Today, Kent House and its land comprise the house itself, Kent and Cole cottages, the garage, garden, plantation and the field to the south of the house and west of Kent House Lane. The barns to the east of Kent House Lane, previously part of the Kent Farm landholding, appear to have been converted in the later 20th century, and are shown to be separately labelled houses by the 1990s. Otherwise, there has been very little change to the land since the 19th century except the removal of a garden building in the 1990s and the construction of the modern garage in place of an earlier building. The house itself has been subject to alteration and restoration in the late 20th century, including removal of internal

walls and changes to the floor plan, following an approved consent application in 1996, and many of the more modern internal and external elements of the building are of this date.

4. DESCRIPTION AND SIGNIFICANCE OF THE SITE

Listed Building Description

4.1 The proposed development site is located within the eastern yard and driveway area of Kent House. Kent House is a residential building, located to the west of Kent House Lane and set in a yard with a garage and drive to the east, and a pair of cottages (Kent Cottage and Cole Cottage) to the north. A garden is located to the west and south, and the land extends to encompass a field which runs along Kent House Lane down to Elstead Road.

4.2 The listed building description, as added to the National Heritage List in June 1959 (ID 1025987), is as follows:

SU 7819-7919 HARTING KENT HOUSE LANE East Harting 28/38 Kent House 18.6.59 II House. C18. Red brick. Stringcourse, dentil course and parapet. Centre window- bay projects with parapet over. Slate roof. Glazing bars intact. Porch with Doric columns and pediment, the sides later enclosed. Doorway in it with semi- circular fanlight. Two storeys and attic. Three windows. Two dormers.

4.3 As the listed building description states, the house dates from the 18th century. Due to the early date of the listed building description, only the basic external features of the principal façade are described. Guidance has been followed to determine the status of the other buildings on the land within which Kent House sits⁴. The walled garden and shed, Cole Cottage and Kent Cottage are deemed to be within the curtilage of the listed building having been part of the land prior to June 1948 and ancillary to the house at time of listing. The double garage is of modern construction, timber on a base of brick, and is therefore not deemed to be curtilage listed as it was not an ancillary structure prior to 1949 or at the time the building was listed. The setting of the listed building comprises these structures including the garage, the yard and garden, and the adjacent fields which give a rural character; though now in separate ownership and having been converted, the barns to the east of Kent House Lane also contribute to the setting of Kent House, illustrating the former extent of the farm and its purpose within the surrounding land.

⁴ Listed Buildings and Curtilage: Advice Note 10, Historic England, February 2018

External Description of Kent House and its Setting

- 4.4 This description is intended to allow a consideration of how Kent House appears within and relates to its setting, including the garage to the east.
- 4.5 Externally, the building consists of a main rectangular building, with a later rectangular rear extension forming an L-shape to the north-west. The two storeys are of red brick: in Flemish bond to the principal southern elevation, but the side elevations of the main section are in English bond and the rear extension and rear wall of the main building is constructed in Flemish Garden Wall or Sussex bond. The brick colour is also slightly different to each elevation. The different bond patterns and brick colours indicate the stages in which the building may have been constructed, taken alongside the historical evidence within Section 3 of this report; The main section of the building may date to the very late or 17th or early 18th centuries, correlating with the development of the Uppark estate, with a principal façade 'front' and roof shape added later in the 18th century using the more decorative Flemish bond. The rear extension, ancillary to the main house, and the rear wall of the main section are possibly of 19th century date and use Sussex bond.
- 4.6 The hipped roof of the main section and the roof of the rear section is covered with relatively small blue slates; the slates appear to be in very good condition and may potentially have been replaced during the late 20th century as they have a particularly clean appearance, as do the ridge tiles of the main roof. There is one conservation rooflight to the eastern hip of the roof, and two to the rear slope. A tall, wide, and slightly projecting brick chimney stack sits to each side of the main building behind the return of the decorative principal faced; each has a rendered section to the first-floor level which may indicate a past repair or scheme to strengthen the stacks. Two further, slimmer stacks sit to the western elevation, alongside the rear section of the building. All have clay pots.
- 4.7 The principal elevation faces south, over a lawned garden and ha-ha and beyond to a pasture field. The façade has three bays, the central bay projecting slightly and being topped with a triangular Corinthian pediment. At ground floor, two sash windows (eight over eight) flank the central entrance; the windows have white painted timber frames above stone cills, and stone flat-arched headers. The stucco entrance porch is carried by Doric columns at the top of shallow stone steps, though as described in the listed building description, the sides of the porch have been infilled later. The porch is capped by an open pediment, below which the timber entrance door has a round-arched fanlight with white-painted glazing bars. There is a simple string course below the first floor level, above which are three 8 over 8 sash windows in the same style as those at ground floor level, and corresponding

in position to the two windows and door below. To the flanking bays, a dentilled cornice sits above these windows, and below a stone capped brick parapet. To the central bay, the previously mentioned pediment has dentilled decoration and sits in front of the brick parapet. This elevation holds the primary architectural interest of the building, and as such was the principal focus of the listed building description.

- 4.8 The western elevation faces onto the garden and towards the rear is joined by the walled garden boundary. To the right, the short return of the principal façade carries round the string course and cornice, and to the left of this is the previously mentioned wide chimney stack. There are four uneven bays across the elevation; bay one to the left of the chimney has a timber framed, glazed door ground floor, accessed by modern steps with a handrail. Above this at first floor level is a six over six timber sash window with a brick arched header. To the roof is a dormer with three panels of casement window. To the left again, bay two has a timber sash window to match that in bay one, at both levels. Beyond the first previously mentioned slim chimney stack which marks the transition to the rear portion of the house, bay three has no opening at ground floor level, and a six over six sash window at first floor level; this window is taller than those to the right on the main part of the house. To the left again is another chimney stack, this time flush to the wall. Bay four beyond is slightly recessed, again is blank at ground floor and has a tall sash at first floor level.
- 4.9 The eastern elevation faces the yard, now used for parking, and ancillary buildings. As with the western elevation, the return of the principal façade wraps round and carries the string course and cornice up to the wide chimney stack. There follow, to the right, two bays on the main part of the building; the first has six over six sash windows with brick headers at ground and first floor level. The second bay is beneath a steep roof pitch which runs to the rear elevation of the main section of the house, and has a six over six sash at a lower level than that in the previous bay. There is also a small square casement window at ground floor level.
- 4.10 The rear elevation of the main section of the building runs to connect with the rear extension. There is a timber two over two sash window at ground floor level on the left hand side, and a timber door to the right hand side. At first floor level is a small, central timber framed two over two sash window. The east facing elevation of the rear extension then returns, with two large twinned two over two sash window within timber frames at ground floor level, and two smaller two over two timber framed sash windows with slim glazing bars at first floor level. An open, rustic portico with a slate roof and timber pillars on brick bases runs the length of this elevation and provides a porch to the rear entrance door; this structure was in place by 1973 and is shown on an aerial photograph of that date (Appendix 1,

Map 9), though it appears relatively modern and may have been renewed more recently. Finally, the northern elevation of the rear extension is largely blank, with one large twinned two over two sash window under a round brick arch to the left hand side of the ground floor. At its western edge the elevation connects to the wall of the walled garden. The style of the ground floor windows to the north and east elevations of the rear extension, and the width of the glazing bars, suggest that they have been inserted at a later date, probably during the early-to-mid 20th century.

- 4.11 The immediate setting of the building is its garden and yard area, adjacent to the house, and these areas tend to correlate with the formal and informal/utilitarian parts of the house. The lawned garden area to the south and south-east of the house, which has a ha-ha to its southern boundary and faces out over a field which has historically been in the ownership of Kent House (or Kent Farm as was), provides a gentle, formal context for the principal façade and main part of the building housing the principal rooms. A secondary access point from the Dining Room also leads out onto a lawned area, and faces a historic plantation which provides a more informal, 'hidden' pleasure garden. To the east and west of the rear portion of the house are more utilitarian spaces; the walled garden to the west is likely to have been built to assist the provision of food and fruit for the household. The driveway and yard areas for parking, which were historically the farmstead yard, are to the east and rear, linking the ancillary buildings of the property including the modern garage but separated visually from the more formal parts of the house. In a way Kent House is a microcosm of a typical grand country residence, and the layout of the grounds contribute to an understanding of the purpose of this historic gentleman farmer's residence and the way in which the formal domestic aspects of life were kept apart from the utilitarian and service areas. Beyond this, the rural context of the house, including the barns (now in separate ownership) to the east and the fields adjacent, also contribute to the value of the historic building, again giving legibility to the development history of the land and property.

Heritage Value of the Assets

- 4.12 Kent House has architectural and artistic value, predominantly in its retained exterior form and details including timber sash windows and high-quality principal façade. The rear portion of the house is of equal interest, but less due to its high quality; its interest lies in the differences between it and the older part of the building, particularly in the style of its fenestration and brick pattern. Internally, the plan form is of interest in that the principal rooms have been retained in a recognisably authentic form, and the development of the house is legible through the juxtaposition of internal and external features.

- 4.13 The house also has historical value in showing the narrative of an 18th century domestic residence, of some local importance but in some ways quite small and simple, in harmony with its land and outbuildings and well suited to the gentleman-farmer for whom it was intended. The continued incremental changes to the house, and the restoration of features in a historic style, have not diminished this narrative; rather they further the story of a family home in use over centuries. The potential for the house to have replaced or re-fronted an earlier building gives the site some archaeological importance, in that historic fabric dating from before the mid-late 18th century may be present.
- 4.14 The setting of Kent House contributes to the legibility of this narrative, and as described above gives a context to the development and purpose of the house. The yard area, the ancillary buildings including Kent Cottage and Cole Cottage have been in farmyard use historically and the buildings including the garage have clustered around the access points of the property from Kent House Lane. The site of the garage and the adjacent domestic oil tank is approximately in the area of the former cart shed mentioned in Section 3 of this report and shown on the earliest estate plan; its siting in relation to the house and as part of the setting of the listed building is historic and makes a contribution to the heritage value of Kent House.

5. IMPACT ASSESSMENT AND JUSTIFICATION

Extent of the works

- 5.1 Full details of the scheme can be found in the submitted drawings and associated Design and Access Statement. No works will be undertaken to Kent House or any other part of the property except for the garage and domestic oil tank.
- 5.2 The existing garage to the east of Kent House will be demolished. A new, open-sided cart-shed style garage will be erected in its place and extending slightly to the south. The existing domestic oil tank will be moved to the south, sited alongside the eastern property boundary.
- 5.3 The new structure will have a plinth of reclaimed brick, with timber posts and a natural slate hipped roof. The western elevation will be predominantly open to provide car access; to the southern end will be a small storage area with a door, constructed with charred ship-lap cladding. The east, north and south elevations will also use this material. The oil tank will be in the same form as it is at present; a plastic tank on a brick plinth.

Design Justification and Impact Assessment

- 5.4 The proposed garage has been designed to provide a traditionally styled garage facility for two cars. The new structure relates to the history of the yard, being in a 'cart-shed' form and open-sided. The materials used are in keeping with the character of the yard area and have been chosen to reflect those present on Kent and Cole Cottage and the barns to the east of Kent House Lane. In particular the timber and natural slate form of the garage allows some legibility of the historic use of this area of the property. The extension in floor size to the garage is minimal, and is mitigated in part by the use of these sensitively chosen materials as well as the slight reduction in roofline, which will ensure the garage is no more dominant within the yard of Kent House than that which exists. In effect, the situation and visual character will not change.
- 5.5 The domestic oil tank, which is necessary to provide fuel for heating Kent House, will be re-sited to allow the extension of the garage footprint to take place. The tank is currently partially hidden behind hedging, and this will be replicated in the proposed design to ensure that this relatively unsightly element is minimally visible.

5.6 The new garage and relocated oil tank will be within the setting of Kent House. As discussed above, the contribution made by the setting of Kent House is related to the legibility of function shown by the garden and yard areas, in particular in respect of how the different parts of the house and garden were used historically. Therefore the demolition of the current garage and its replacement with a larger garage, and the re-located oil tank will not cause harm to the heritage value of Kent House in general. However, it is acknowledged that the design of the garage is key in ensuring that no harm results from its construction. As noted, the design reflects the historic nature of the yard at this point, re-creating a former cart-shed which had formed part of the site in the 18th century. As it is an ancillary building within the utilitarian area of the grounds of Kent House – the yard – the new garage and relocated oil tank behind hedging will appear in keeping within the view of Kent House, particularly its eastern elevation, and continue to define the southern access point to the yard as has been the case for many years. The historic separation between utility and formality in the ground of Kent House will be retained. It is considered therefore that no harm to the heritage value of Kent House due to the change in its setting will arise from the construction and presence of the proposed garage and relocated oil tanker.

Conclusions

5.7 In summary, the existing modern garage will be demolished. The proposed garage and relocated oil tanker will be in the yard to the east of the primary listed building, on the site of the current garage, and within the setting of Kent House.


5.8 It is assessed that there will be no harm to the special architectural and historic interest of the heritage asset as set out in the NPPF, due to the minimal change to the setting of Kent House, and the sympathetic and traditional style and siting of the proposed structure.

5.9 The plan form of Kent House and its grounds, and their legibility, will be retained, and extant historic structures respected. The design adheres to South Downs Local Plan policy SD1 in that it conserves and enhances the cultural heritage of the area. The loss of historic fabric has been avoided as the existing garage is modern and the design has been carefully considered to respect the character of the ;listed building and retain its setting, adhering to policy SD13.

5.10 The proposed works will allow the current owners of the building to comfortably continue as custodians for this listed building, caring for it and securing the safe use and maintenance of the building for the foreseeable future, whilst retaining its heritage value and architectural interest.

APPENDIX 1: HISTORIC MAPPING

Map 1: 1750 (Sussex Estate Maps: Harting)



Map 2: 1785 (Uppark MSS 501)



Map 3: 1840 (Tithe Map)



Map 4: 1875 (Ordnance Survey 1:2,500)

On following page.


Sussex

Published 1875


Source map scale - 1:2,500

The historical maps shown were reproduced from maps predominantly held at the scale adopted for England, Wales and Scotland in the 1840's. In 1854 the 1:2,500 scale was adopted for mapping urban areas and by 1896 it covered the whole of what were considered to be the cultivated parts of Great Britain. The published date given below is often some years later than the surveyed date. Before 1938, all OS maps were based on the Cassini Projection, with independent surveys of a single county or group of counties, giving rise to significant inaccuracies in outlying areas.

Map Name(s) and Date(s)



Historical Map - Segment A13




Order Details

Order Number: 305862862_1_1
 Customer Ref: KENT2301
 National Grid Reference: 479390, 119570
 Slice: A
 Site Area (Ha): 0.01
 Search Buffer (m): 100

Site Details

Kent House, East Harting, PETERSFIELD, GU31 5LS



Map 5: 1898 (Ordnance Survey 1:2,500)

On following page.


Sussex

Published 1898


Source map scale - 1:2,500

The historical maps shown were reproduced from maps predominantly held at the scale adopted for England, Wales and Scotland in the 1840's. In 1854 the 1:2,500 scale was adopted for mapping urban areas and by 1896 it covered the whole of what were considered to be the cultivated parts of Great Britain. The published date given below is often some years later than the surveyed date. Before 1938, all OS maps were based on the Cassini Projection, with independent surveys of a single county or group of counties, giving rise to significant inaccuracies in outlying areas.

Map Name(s) and Date(s)



Historical Map - Segment A13




Order Details

Order Number: 305862862_1_1
 Customer Ref: KENT2301
 National Grid Reference: 479390, 119570
 Slice: A
 Site Area (Ha): 0.01
 Search Buffer (m): 100

Site Details

Kent House, East Harting, PETERSFIELD, GU31 5LS




Map 6: 1912 (1:2,500)


On following page.

The historical maps shown were reproduced from maps predominantly held at the scale adopted for England, Wales and Scotland in the 1840's. In 1854 the 1:2,500 scale was adopted for mapping urban areas and by 1896 it covered the whole of what were considered to be the cultivated parts of Great Britain. The published date given below is often some years later than the surveyed date. Before 1938, all OS maps were based on the Cassini Projection, with independent surveys of a single county or group of counties, giving rise to significant inaccuracies in outlying areas.

Map Name(s) and Date(s)



Historical Map - Segment A13




Order Details

Order Number: 305862862_1_1
 Customer Ref: KENT2301
 National Grid Reference: 479390, 119570
 Slice: A
 Site Area (Ha): 0.01
 Search Buffer (m): 100

Site Details

Kent House, East Harting, PETERSFIELD, GU31 5LS



Map 7: 1946, Aerial Photograph (16th April 1946, Historic England (RAF photography))



Map 8: 1973 Aerial Photograph (Copyright held by Ordnance Survey)



Map 9: 1971 (1:2,500)

On following page.


Ordnance Survey Plan

Published 1971


Source map scale - 1:2,500

The historical maps shown were reproduced from maps predominantly held at the scale adopted for England, Wales and Scotland in the 1840's. In 1854 the 1:2,500 scale was adopted for mapping urban areas and by 1896 it covered the whole of what were considered to be the cultivated parts of Great Britain. The published date given below is often some years later than the surveyed date. Before 1938, all OS maps were based on the Cassini Projection, with independent surveys of a single county or group of counties, giving rise to significant inaccuracies in outlying areas.

Map Name(s) and Date(s)



Historical Map - Segment A13



Order Details

Order Number: 305862862_1_1
 Customer Ref: KENT2301
 National Grid Reference: 479390, 119570
 Slice: A
 Site Area (Ha): 0.01
 Search Buffer (m): 100

Site Details

Kent House, East Harting, PETERSFIELD, GU31 5LS

