

## Project Summary



**1. Study**  
Quantity: 1  
Supply & Fit - Remove & replace

Traditional Flush Casement



**2. Hallway Landing**  
Quantity: 1  
Supply & Fit - Remove & replace

Traditional Flush Casement



**3. Bed**  
Quantity: 1  
Supply & Fit - Remove & replace

Traditional Flush Casement

### Quotation for:

Roderick Sloan  
Westrip Farm  
Westrip  
Stroud  
Gloucestershire  
GL6 6HA

### Prepared by:

### Site Address:

Westrip Farm Westrip Stroud Gloucestershire United Kingdom, GL6 6HA

### Lead time:

Usually 8-10 weeks from point of survey

### Guarantee:

10-Year

### Payment terms:

Price is valid for 21 days and subject to any changes required at technical survey. 50% deposit due at technical survey and 50% balance due on installation.

### Payment schedule:

Deposit (50%):	£4,540.15
Balance (50%):	£4,540.14

Technical detail: 1 - Study - Supply & Fit - Remove & replace

Quantity: 1

☀ Viewed from outside



☀ Viewed from inside



## Traditional Flush Casement

- Species:** Redwood FJ
- Frame LR:** Trad Flush CMT Outer Frame Jamb 56mm
- Frame Top:** Trad Flush CMT Outer Frame Head 58mm
- Sash Bottom:** Trad Flush CMT Sash B Rail 56 x 78mm
- Sash LRT:** Trad Flush CMT Sash 56 x 56mm
- Mullion:** Traditional Flush CMT Mull 75mm
- Bead:** Trad CMT 24mm Bead
- Cill species:** Meranti
- Cill:** Sub Cill With Nosing 227mm (87+140) x 38mm Cill
- Head drip:** Head Drip
- Astragal bar:** 16mm Lambs Tongue

**Colour:** Bereco Collection Traffic White Satin


**Window Handle:** Connoisseur Brass Plated

**Easy clean hinge:** Yes

**Night Vent Facility:** Night Vent Facility x1

**Custom Extra:** Match Head Arch On Openers

**Glass:** 31dB Std Float 4/16Ar/4T - Warm Edge Black - back to back spacer - Clear



Technical detail: 2 - Hallway Landing - Supply & Fit - Remove & replace

Quantity: 1

☀ Viewed from outside



☀ Viewed from inside



## Traditional Flush Casement

- Species:** Redwood FJ
- Frame LR:** Trad Flush CMT Outer Frame Jamb 56mm
- Frame Top:** Trad Flush CMT Outer Frame Head 58mm
- Sash Bottom:** Trad Flush CMT Sash B Rail 56 x 78mm
- Sash LRT:** Trad Flush CMT Sash 56 x 56mm
- Mullion:** Traditional Flush CMT Mull 75mm
- Bead:** Trad CMT 24mm Bead
- Cill species:** Meranti
- Cill:** Sub Cill With Nosing 227mm (87+140) x 38mm Cill
- Head drip:** Head Drip
- Astragal bar:** 16mm Lambs Tongue

**Colour:** Bereco Collection Traffic White Satin


**Window Handle:** Connoisseur Brass Plated

**Easy clean hinge:** Yes

**Night Vent Facility:** Night Vent Facility x1

**Custom Extra:** Match Head Arch On Openers

**Glass:** 31dB Std Float 4/16Ar/4T - Warm Edge Black - back to back spacer - Clear



Technical detail: 3 - Bed - Supply & Fit - Remove & replace

Quantity: 1

☀ Viewed from outside



☀ Viewed from inside



## Traditional Flush Casement

**Species:** Redwood FJ  
**Frame LR:** Trad Flush CMT Outer Frame Jamb 56mm  
**Frame Top:** Trad Flush CMT Outer Frame Head 58mm  
**Sash Bottom:** Trad Flush CMT Sash B Rail 56 x 78mm  
**Sash LRT:** Trad Flush CMT Sash 56 x 56mm  
**Mullion:** Traditional Flush CMT Mull 75mm  
**Bead:** Trad CMT 24mm Bead  
**Cill species:** Meranti  
**Cill:** Sub Cill With Nosing 227mm (87+140) x 38mm Cill  
**Head drip:** Head Drip  
**Astragal bar:** 16mm Lambs Tongue

**Colour:** Bereco Collection Traffic White Satin


**Window Handle:** Connoisseur Brass Plated

**Easy clean hinge:** Yes

**Night Vent Facility:** Night Vent Facility x1

**Custom Extra:** Match Head Arch On Openers

**Glass:** 31dB Std Float 4/16Ar/4T - Warm Edge Black - back to back spacer - Clear



# BERECO HIGH PERFORMANCE TIMBER WINDOWS & DOORS



## CHOOSE YOUR TIMBER

Both softwood and hardwood come with the same 30 year warranty against rot and fungal infection and 10 year warranty on the factory applied coatings.

### Softwood. Redwood

All our redwood is slow grown from Europe and harvested at between 90 and 130 years of age. It features a smooth surface, and achieves excellent durability even without preservative treatment. Perfect for painted finishes.

### Hardwood. Dark Red Meranti

Our hardwood comes with full chain of custody. It features a pitted effect surface and a natural red hue to the timber perfect for stain finishes.

### FSC® 100%

Bereco use only FSC® 100% timber in our wooden windows and doors.

## CHOOSE YOUR GLAZING

### 24mm Double Glazing

Soft coat low e argon filled high performance double glazing with a centre pane u value of 1.0 W/m²K.

### 14mm SlimLine Double Glazing

Krypton gas filled as standard our narrow cavity units offer a u value of just 1.2W/m²K

### Acoustic Double Glazing

Available on both contemporary and traditional ranges our acoustic double glazing offers decibel ratings of up to 46dB.

### Triple Glazing

Our Performance enhancing triple glazing available on both contemporary and traditional ranges offers centre pane u values as low as 0.5W/m²K

### Specialist Glazing

Self-cleaning; solar control glass; painted and coloured glass are also available.

## CHOOSE YOUR FINISH

Bereco are one of the few companies to offer dual colour paint and stain options to suit internal décor and external façade.

### Paint It

Introduce a splash of colour with any BS or RAL paint finish to create a truly unique design statement.

### Match It

We can match any Farrow & Ball colour where a traditional finish is desired.

### Stain It

A wide range of stain options are available combined with clear timber to achieve a seamless finish.

### Frame It

Create a statement entrance with a range of contrasting frame and leaf dual colour options.



Bereco Retail, Unit 4-5, Aspen Court,  
Centurion Business Park, Rotherham,  
South Yorkshire, S60 1FB.


+44 (0) 1709 377406  
www.bereco.co.uk  
enquiries@berecoretail.co.uk

## OUR PRODUCTS



### Sliding Sash Windows

Available in spiral balance or cords & weights styles; products are internally glazed & feature double weatherstrips & cutting edge glazing options.



### Casement Windows

Bereco Timber Casement Windows offer excellent weather ratings and high security espagnolette locking system with friction hinges as standard.



### Tilt & Turn Windows

The large sash and glass sizes of our tilt and turn windows enable flexibility in design with the creation of screens and large glazed areas adding impact to any property.



### Feature Windows

From large screens to curved, angled and shaped, our team can help you design products individually tailored to your property.




### Entrance Doors

Bereco bespoke timber Entrance Doors offer the finest high performance components, secure locking systems, laminated glazing and 3D adjustable hinges as standard.



### Modern Creative Entrance Doors

Bereco Creative Range Entrance Doors are an exclusive collection of 10 ultra-modern door designs crafted using sharp lines and flush panels.



### French Doors

Bereco offer French Doors in single or double leaf configurations with various threshold options in either a flush or lipped design.



### Folding Doors

Bereco folding doors are available in configurations of up to 10 leaves, spanning up to 10 metres wide and can open up the entire side of a property.



### Patio Doors

Create open spaces with our large spanning timber sliding patio doors, operated and carried safely and effortlessly without the use of force.