



Note:  
Prescot Road is subject to a 50mph speed limit.

To establish actual speeds, a 7 day ATC speed survey was undertaken between 6th April and 12th April 2023.

The southbound observed 7-day 85th percentile speed is 47.7mph.

According to the standards set out in DMRB, the required visibility is 160m.

Visibility splays 2.4m x 160m measured from 5m intersections along site frontage.

Visibility is sufficient

Site frontage on Melling Road

29.0m

B 5197

Arrochar

Fountain

The Chesterfield

Proposed Residential Development  
Arrochar Prescot Road Melling  
Access Appraisal  
Visibility Splays to the North  
Drawing 1150-SK2  
Scale 1:1000@A3  
Issued 26/04/2023