

| | 100mm ON ORIGINAL DRAWING | | |
|-----------------------|---|--|--|
| DRAWING | NOTES | | |
| . THESE D 10755-00 | RAWINGS TO BE READ IN CONJUNCTION WITH DRAWIN 1. | | |
| SAFETY | HEALTH & ENVIRONMENTAL | | |
| RISK | SIGNIFICANT DESIGNER IDENTIFIED HAZARDS | | |
| REF | HAZARD | | |
| A | PROPOSED STRUCTURE DESIGNED IN ACCORDANCE WITH CURRENT STANDARDS AS FAR AS IS REASONABLY PRACTICABLE. APPROVAL AND RELEVANT DEROGATIONS TO BE SOUGHT AND APPROVED. | | |
| В | WORKING ADJACENT TO RAILWAY, WORK AT HEIGHT AND LIFTING OPERATIONS. WORKS ON OR NEAR THE LINE TO BE UNDERTAKEN IN ACCORDANCE WITH NETWORK RAIL WORK PROCEDURES. | | |
| С | DEMOLITION OF EXISTING STRUCTURE. CONTRACTOR TO DESIGN NECESSARY TEMPORARY WORKS AND DETERMINE SAFE DEMOLITION SEQUENCE & LIFTING PLAN FOR EXISTING STRUCTURE. | | |
| D | CONDITION OF EXISTING TRESTLES. ADDITIONAL STRENGTHENING/RENEWAL OF SUBSTRUCTURES TO BE IMPLEMENTED PRIOR TO INSTALLATION OF NEW MAIN SPAN. | | |
| E | CONDITION OF EXISTING FOUNDATIONS. RENEWAL OF FOUNDATIONS TO BE IMPLEMENTED PRIOR TO INSTALLATION (NEW MAIN SPAN. | | |
| F | EXISTING SERVICES. SERVICES TO BE IDENTIFIED, TRACED AND ISOLATED AND TEMPORARILY SUPPORTED PRIOR TO WORKS. SUITABLE PROTECTION MEASURES TO BE UNDERTAKEN BY CONTRACTOR PRIOR TO INSTALLATION. | | |
| G | EXISTING STAIRS AND LANDING PARAPETS TO BE TEMPORARILY SUPPORTED OR REMOVED DURING WORKS. SEE TEMPORARY WORKS SUBMISSION FOR DETAILS. | | |
| Н | RAIL IMPACT LOADS DUE TO STRUCTURE CLEARANCE. RESIDUAL RISK. | | |
| I | LIFTING POINTS DESIGNED FOR VERTICAL LOADS ONLY. LIFTING BEAMS TO BE UTILISED TO ENSURE VERTICAL LOADING APPLIED TO LIFTING POINTS DURING LIFTING PROCEDURES | | |
| J | STAIR RISER HEIGHTS. MAY NOT BE POSSIBLE TO ACHIEVE UNIFORM & COMPLIANT RISERS ON LOWER CONCRETE STEPS WHERE PLATFORM LEVEL DICTATES AND TOP STEP WHERE EXISTING TRESTLE DICTATES RISER HEIGHT AND TREAD LENGTH. | | |
| К | TIMBER TREAD SLIP RESISTANCE TO BE TESTING IN ACCORDANCE WITH SPECIFICATION NOTE PRIOR TO FABRICATION. TEST RESULTS TO BE PROVIDED TO NETWORK RAIL. | | |
| L | GEOTECHNICAL PARAMETERS TO BE VERIFIED PRIOR TO UNDERTAKING WORKS. POSSIBLE GROUND REMEDIATION/FOUNDATION REDESIGN REQUIRED SHOULD VALUES LISTED NOT BE ACHIEVED. | | |

20

20

0

40

60

| D | FORM B (4) ISSUE | NR | BTB | BTB | 06.10.23 |
|-----|------------------|-----|-----|-----|----------|
| С | FORM B (3) ISSUE | NR | BTB | BTB | 22.02.23 |
| В | FORM B (2) ISSUE | NR | SC | BTB | 15.12.22 |
| А | FORM B (1) ISSUE | NR | SC | BTB | 18.03.22 |
| REV | AMENDMENT | DRN | CHK | APP | DATE |
| | | | | | |





PROJECT TITLE BRADING STATION FOOTBRIDGE ELR - IOW STRUCTURE No. EW1/25 MILEAGE - 4m 1166yds

PROPOSED TRESTLE STRENGTHENING FRAME

DRAWING TITLE

| DRAWN | СНК | APP | DATE | SCALE |
|--------------|-----|-----|-------------|----------------|
| NR | SC | BTB | FEB 22 | AS SHOWN AT A1 |
| JOB NUMBER D | | | WING NUMBER | REVISION |
| 10755 | | | 107 | D |