



*** TREE PROTECTION BARRIER TO BS5837 : 2012.**
 Protective barriers should be erected prior to the commencement of any site clearance, demolition, or development. No storage within the construction exclusion zone (Fenced Areas).
 The fencing should utilise a scaffold framework in accordance with BS5837 : 2012.
 Weldmesh panels should be set in rubber block supports and cable tied or clamped with scaffold clamps to the adjacent panel.
 The protective fencing should be erected as shown on the proposed site plan & should not be moved unless agreed with the local planning authority Arboriculturist.
 Informative's should be placed on barriers at 1.5 metres in height at 3 metre intervals facing outwards.
 Informative's should clearly provide details of the tree zone & correct procedures.

*** Provide Protective Fencing To The Western Site Boundary To Protect The Trees On The Neighbouring Site During The Full Construction Period.**

PROPOSED SITE PLAN.
 SCALE 1:500.

Contract
PROPOSED REPLACEMENT BARN DWELLING & CONVERSION OF EXISTING BARN DWELLING TO STORE/WORKSHOP AT "PINOCCHIOS", MILL LANE, BRADFIELD, MANNINGTREE, ESSEX. CO11 2QP.

Title
PROPOSED SITE PLAN.

Client
MR & MRS B. RHYS-LEWIS.

REV	DATE	DESCRIPTION
P		

Scale 1:500.
 Date DECEMBER 2023.
 Drawn S. TANKARD

Drawing No.
29-2023-07