

ROOF, R1:

- Roof sheet metal
- Frame for roof plate 25x100 c/c250
- Ventilation batten 48x73 c/c600
- Wind proof Solitex Mento 3000
- Roof rafter 48x198 c/c600+insulation
- Batten for assembly of the insulation 48x148 c/c600
- +insulation
- Vapour barrier Intello XN
- Fixing batten 22x100 c/c600

EXTERNAL WALL, EW1


- Laminated log LH 94x160
- Proprietary breather membrane (Tyvek or equal)
- Frame 48x198 c/c600+insulation
- Vapour barrier Intello XN
- Log board HP 20x160

SUSPENDED CEILING, SC2:

- Suspended ceiling joist 48x148 c/c600
- Fixing batten 22x100 c/c600
- Ceiling board STVM 15x120

GROUND FLOOR, F1:

- Floor covering
- Reinforced concrete slab
- Insulation

tunnus	lukum.	muutos	muuttanut	päiväys	
Kaup.osa/Kylä	Korttel/Tila	Tonttimo	Viranomaisen merkintä		
Rakennustoimenpide	New building		Piirustustaji	Juoks.no	
Rakennuskohteen nimi ja osoite	Peter and Lisa Smith		Piirustuksen sisältö	Mittakaava	
			Section B-B	1:50	
			Työn no	X	
			Piirt.	Suunnitteluala	Piir.no
			Tark.	ARK	4
Päiväys	13.11.2023		Korvaa no:n	Korvattu numerolla	
	Vesa Lassila, RI				