Plant Schedule

TREES

No.	Ref.	Species	Common name	Size	Notes
3	Ap	*Acer platanoides*	Norway maple	8-10cm Girth Standard Root Ball	Location as shown
6	Bp	*Betula pendula*	Silver birch	8-10cm Girth Standard Root Ball	
4	Ca	*Corylus avellana*	Hazel	Multistem, 2.5-3m, Root Ball	
3	Me	Malus Evereste	Crab apple	8-10cm Girth Standard Root Ball	
3	Pa	Prunus avium	Wild cherry	8-10cm Girth Standard Root Ball	
5	Sa	*Sorbus aucuparia*	Rowan	8-10cm Girth Standard Root Ball	

HEDGES

No.	Ref.	Species	Common name	Size	Notes
250	Cb	*Carpinus betulus*	Hornbeam	60-80cm BR	Double staggered hedge with training fence, 5/lm

SHRUBS

No.	Ref.	Species	Common name	Size	Notes
145	Ec	*Erica carnea f. alba 'Whitehall'*	Winter heath heather	3L CG	9 plants per m²
170	Hp	*Hebe pinguifolia 'Sutherlandii'*	Shrubby veronica	3L CG	
55	Jn	*Juniperus Nana*	Dwarf juniper	3L CG	
150	Pt	*Pachysandra terminalis*	Japanese spurge	3L CG	
170	Vm	*Vinca minor f. alba 'Gertrude Jekyll'*	Lesser white periwinkle	3L CG	
135	Vt	*Viburnum tinus*	laurustinus	3L CG	

BULBS

No.	Ref.	Species	Common name	Size	Notes
1300	Cr	*Crocus*	Large flowering crocus	5/+	50/m²
900	Nc	*Narcissus*	Daffodil	12 / 14	30/m²

SEEDING

m²	Ref.	Seed Mix	Supplier	Sowing Rate	
1800	S1	Mavisbank mix	Scotia Seeds	3g/m²	20% wildflower, 80% grasses

Softworks

- Existing Trees — To be retained and protected to BS 5837: 2012
- Proposed Trees — See plant schedule for details; 24inc
- Proposed Hedge planting — See plant schedule for details
- Proposed Shrub planting — See plant schedule for details
- Proposed Seeding — See plant schedule for details
- Proposed Bulb planting — See plant schedule for details

Rev	Date	Description	Drn	Chk	App
P01	19.10.23	First Issue	SH	TM	TM

Scale 1:200

0 2 4 6 8 10m

Do not scale for construction purposes
All dimensions are to be verified on site
© Drawing & design copyright LUC

LUC

www.landuse.co.uk

Project
Stoneywood Gate
for Tinto

Client
CoCity

LUC Job Nr	Scale @A1	Status
12608	1:200	S1

Drawing Title
Softworks General Arrangement

Drawing Nr	Rev
12608-LUC-XX-XX-DR-L-0400	P01