



- Notes:**
- All work to comply with Aberdeen City Council's - Enterprise Planning & Infrastructure guidelines and specification for roads within residential and industrial developments.
 - Prior to roads construction works, the appointed Contractor is to discuss with Aberdeen City Council engineer exact requirement for laboratory CBR PSD & MCV tests. All results must be submitted and details of any coping requirements to the roads officer who is processing the RCC application.
 - Road signs and markings to be in accordance with the Traffic Signs Regulations And General Directions (TSRGD) 2016.
 - The contractor is responsible for checking the line and level of existing services prior to the commencement of works. Any discrepancies from design information must be reported to the Site Manager and Site Engineer in writing.
 - Street occupation should be sought from the local authority prior to works commencing on a public road.
 - Street name plate positions to be agreed on site with Aberdeen City Council prior to installation. Positions shown on road layout drawing are indicative.
 - Visibility splay envelopes to be under the control of the roads authority. Visibility area to be kept clear of planting and obstructions over 600mm high.
 - Non-adopted areas to drain via porous paving or free draining gravel. Where parking areas or driveway's fall towards the adopted carriageway, a channel drain or gully is to be provided to prevent water running onto adopted areas.

- Legend:**
- Denotes extent of tarmac private roads.
 - Denotes extent of paved private footways/footpaths.
 - Denotes Car Parking Non-Pervious Block Paving To remain private and be maintained by factoring agreement. Colour to be agreed with all parties.

A	Project Title updated	GCO	30/10/23
Rev	Revision Description	Initial	Date

Cameron+Ross
 CIVIL + STRUCTURAL ENGINEERING
 Forbes House | 15 Victoria Street | Aberdeen | AB10 1XB
 CameronRoss.co.uk
 Aberdeen 01224 642 400 | Edinburgh 0131 374 7960 | Inverness 01463 570 100

Client:
 CoCity

Project:
 Stoneywood Gate
 Stoneywood Park, Dyce
 Aberdeen

Drawing Title:
 Road Adoption Plan

Status:
 Planning

Scale: 1:200 @ A1 Date: 12/10/2023

By: GCO Checked: RAG Approved: RAG

Dwg. No.
 230736-000-CAM-DR-C-210

Rev.
 A