

Dormer not to be constructed above existing ridge height, and set minimum 200mm back from the eaves

All side facing windows to be obscured glazing and non-opening below 1.7m above floor level.

All rooflights not to protrude more than 150mm beyond the plane of the slope of the original roof.

All external materials to be of a similar appearance to the existing dwelling.

Extractor fan in bathroom to be ducted to outside air
All drainage works to be agreed on site as works progress

S&VP to terminate 900mm above any openings within 3m or to have external AAV fitted no less than 200mm above highest floodable point


0

Notes:
The General contractor is responsible for the verification of all dimensions on site and shall inform the contract administrator of any discrepancies.


Do not scale from this drawing. Use figure dimension only.

Existing foundations, lintels and wall to be exposed if required by Building Control for assessment and upgrading if found inadequate.


Drawings are subject to building control approval



PROPOSED CURB LINE PLAN
SCALE 1:100 @ A2



EXISTING CURB LINE PLAN
SCALE 1:100@ A2



CURB LINE

5m
10m
0 1 2 3 4 5 6 7 8 9 10

STAGE PLANNING

SITE ADDRESS_39 ALBERMARLE GARDENS KT3

PROJECT NAME_Householder Application

DRWG ORDER_Site Plans

DRW NO_A1006-101

REVISION_-

SCALE_1:200 @ A2 Format

DATE_06.11.2023