

DO NOT SCALE, IF IN DOUBT ASK. DO NOT INTERROGATE CAD BASE

| STATION | EASTING | NORTHING | LEVEL (m) |
|---------|------------|------------|-----------|
| A | 333603.305 | 442815.288 | 4.740 |
| B | 333616.387 | 442827.662 | 4.961 |
| C | 333612.138 | 442802.872 | 5.223 |
| D | 333607.472 | 442790.288 | 5.136 |

ABBREVIATIONS

| | | | |
|-----|-------------------|-----|---------------------|
| AV | AIR VALVE/VENT | IC | INSPECT CHAMBER |
| BSL | BOLLARD | IL | INVERT LEVEL |
| BR | BELUSHI BEACON | JKN | JAPANESE KNOTT WEED |
| BM | BENCH MARK | LH | LAMP HOLE |
| BL | BED LEVEL | LP | LAMP POST |
| BS | BUS STOP | NP | NAME PLATE |
| BT | BRITISH TELECOM | WH | WHEEL |
| CL | COVER LEVEL | PS | POST/SIGN POST |
| CS | COVERED | PR | POST BOX |
| DA | DISUSED | PS | UNKNOWN SERVICE |
| EL | ELED LEVEL | RE | RODDING EYE |
| ELE | ELED - JUNCT. BOX | RL | ROD LEVEL |
| EP | ELECTRIFY POLE | RS | ROAD SIGN |
| FI | FIRE HYDRANT | ST | STOP SIGN |
| FL | FLOOR LEVEL | TH | TRAIL HOLE |
| FSS | FULL OF SEDIMENT | TL | TRAFFIC LIGHT |
| FP | FLAG POLE | TP | TELEGRAPH POLE |
| G | GULLY | TV | CABLE TV BOX |
| GM | GAS METER | UL | UNABLE TO LIFT |
| GV | GAS VALVE | WM | WATER METER |



SYMBOLS


| | | | |
|----|----------------|---|------------|
| + | SURVEY STATION | ○ | TREE |
| -E | O/H ELEC CABLE | ○ | BENCH MARK |
| -T | O/H PHONE LINE | ○ | TRIAL PIT |
| - | CANOPY/HEDGE | ○ | BOREHOLE |

NOTES

- A) ONLY MANHOLES AND SERVICES VISIBLE AT TIME OF SURVEY SHOWN
- B) O/S GRID USED AND ORIENTATED TO TRUE NORTH
- C) LEVELS IN METRES RELATED TO G.P.S.
- D) DRAINAGE INFORMATION MUST BE CHECKED PRIOR TO WORK COMMENCING

Rev Description Date
 PROPOSED DEVELOPMENT AT WOODLAND PFS, THORNTON

-  EXISTING IMPERMEABLE AREA: 1360m² (0.136 Ha)
EXISTING SW RUN-OFF: 2.78 x 0.136 x 50 = 18.9 L/S - 74% = 5.0 L/S
-  PROPOSED IMPERMEABLE AREA: 1280m² (0.128 Ha)



| REV. | DATE. | REVISION. | BY. | CHK. |
|------|-------|--------------|-----|------|
| - | - | FIRST ISSUE. | PH | NB |

Penny Petroleum
 Proposed Petrol Filling Station at Woodland S/Strn
 Fleetwood Road N, Thornton-Cleveleys

Impermeable Area Plan

Goodson Associates
 Tel: +44 (0)113 369 7925
 Fax: -
 Email: leeds@goodsons.com
 Web: www.goodsons.com

Consulting Civil, Structural & Transportation Engineers
 Fountain House, 4 South Parade,
 Leeds, LS1 5QX
 Also at Aberdeen, Edinburgh and Glasgow.

PLANNING

| | |
|--------------------------|-------------------|
| DATE CREATED: Sept. '23' | SCALE: 1:250 @ A1 |
| CONTRACT No: P15701 | DRAWING No: 501 |
| REV: - | |