

# MENDIP

A double pantile design with elegant flowing lines, providing instant visual appeal.



## COLOUR AVAILABILITY



Anthracite (S)



Smooth Grey (S)



Antique Brown (G)



Smooth Brown (S)



Old English Dark Red (S)



Mosborough Red (S)

**Key**  
(G) Granular finish  
(S) Smooth finish

## TECHNICAL DATA

|                            |  |  |
|----------------------------|--|--|
| Size of tile               | 420mm x 330mm  |  |
| Minimum pitch*             | 17.5° Smooth (75mm headlap)<br>15° Smooth (100mm headlap)  | 30° Granular (75mm headlap)<br>25° Granular (100mm headlap)    |
| Maximum pitch              | 90°  |  |
| Minimum headlap            | 75mm   |  |
| Maximum gauge              | 345mm  |  |
| Body thickness             | 27mm (nominal)   |  |
| Overall depth              | 59mm   |  |
| Cover width                | 298mm (nominal)  |  |
| Hanging length             | 397mm (nominal)  |  |
| Covering capacity (net)    | 9.7 tiles/m <sup>2</sup> at 75mm headlap   | 10.5 tiles/m <sup>2</sup> at 100mm headlap                     |
| Weight of tiling (approx.) | 46kg/m <sup>2</sup> (0.45 kN/m <sup>2</sup> ) at 75mm headlap  | 49kg/m <sup>2</sup> (0.48 kN/m <sup>2</sup> ) at 100mm headlap |
| Battens required (net)     | 2.9 lin.m/m <sup>2</sup> at 75mm headlap   | 3.1 lin.m/m <sup>2</sup> at 100mm headlap                      |
| Batten size recommended    | 38mm x 25mm for rafters/supports not exceeding 450mm centres (fixed to BS 5534)<br>50mm x 25mm for rafters/supports not exceeding 600mm centres (fixed to BS 5534) |  |
| Tile nails                 | 70mm x 3.35mm  |  |
| Fixing clips               | Eaves, verge and tile clips  |  |
| Authority                  | BS EN 490  |  |

\* The minimum recommended pitch and lap may be influenced by special circumstances, please contact the Technical Advisory Service.

## SUSTAINABILITY

- ✓ A<sup>+</sup> rated in the BRE Green Guide (based on generic rating for UK produced concrete interlocking tiles  
Element Refs: 812410007, 812410018, 812410049)
- ✓ BES 6001 Responsible Sourcing certified

## EXTENDED RAFTER LENGTHS

Mendip interlocking tiles can now perform at extended rafter lengths as follows:

- 15° - 17.5° pitch with a rafter length up to and including 15m will require a 100mm headlap.
- 17.5° pitch and above with a rafter length up to and including 15m will require a 75mm headlap.

