

System 10 | FlushSash Casement Window

# Features

## **Technical Drawing**

Maximum sash size Side hung: 620mm (w) x 1270mm (h)

#### **Outer frames**

56mm, 72mm and 84mm outer frames

#### Mullions

70mm or 95mm mullions

#### Sash

61mm flush sash

### Finishes

Available in a large assortment of colours and woodgrain options from the Variations range and SPECTRAL\*

### **Glazing beads**

28mm bevelled 28mm sculptured 32mm bevelled 36mm bevelled

### Ancillaries

Frame extensions, cills and weathering trims Range of coupling options Range of bay pole options

## Thermal performance\*\*

Achieves U-values as low as 1.3 W/m<sup>2</sup>K using double glazing Achieves U-values as low as 1.1 W/m<sup>2</sup>K using triple glazing

\* SPECTRAL is only available on bevelled or flat surfaces.

\*\* Figures can vary dependent on specification.





