

NOTES:

Existing masonry wall to be retained.

Masonry wall to be demolished

Windows and doors to be removed and

existing wall re-built / made good.

1. ALL PROPOSALS ARE DRAWN AS HAND.

ALL DRAWINGS AT 1:50 SCALE UNLESS STATED OTHERWISE.

3. DO NOT SCALE DRAWINGS - USE FIGURED DIMENSIONS ONLY.

4. ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE STATED.

ALL DIMENSIONS TO BE CHECKED ON SITE.
 DRAWING TO BE READ IN ACCORDANCE WITH ALL CURRENT SCHEDULE, SPECIFICATIONS, STANDARD CONSTRUCTION DETAILS, PLUS ALL BESPOKE CONSTRUCTION DETAILS RELEVANT TO

ANY INACCURACIES FOUND ON THE DRAWINGS
 OR SPECIFICATIONS ARE TO BE REPORTED TO
 THE ARCHITECT IMMEDIATELY.

NO. HAZARD:

Corona Virus - All works are to be carried out following the latest guidance from the Government, HSE and Public Health England. The Principle Contractor is to make a daily review of any changes to the guidance and liaise with the Client in regards to required changes in working practices.

Paclitites - Welfare facilities, site security, material unloading / storage and waste storage areas to be confirmed by the client of the works. The Principle Contractor will need to coordinate safe access into the site for the Client in addition to any access required for the works.

Asbestos Survey - Survey required and no works are to be carried out until one has been undertaken.

Incomplete records - Incomplete records of previously installed services, beware of concealed services below ground and within structures etc.

Below ground drainage - Full route of below ground drainage layout unknown, to be confirmed including connection to mains.

Live Services - installed on site to serve the Farmhouse and to be maintained during the works where possible. The Principle Contractor is to liaise with the Client to inform them when services will be interrupted.

High level wires - Telegraph poles are close to the works. Beware of existing high level power wires running across proposal area and possible access routes for machinery connecting from adjacent pole to Barn 2.

Site Boundary - The building is close to the site boundary (less than a metre). Limited access for works in close proximity to site boundary, scaffolding etc.

Access Road - Limited width access road to site will limit the size of vehicles accessing the site for delivery etc.

Stability of structure - Existing structure may require shoring / support / rebuilding in areas where demolition works are occurring.

Team Sign Off Status:

| Issued for: | PLANNING | | Project No: | 1492009 | | LEY FARM | Dwg No: | YARCOMBE | PP02 | |

Drawing:
BARN 1 + 2 PROPOSED
GROUND FLOOR PLAN

Out building for plant for Unit 1.

Indicative location for hot water

cylinder to be confirmed by

mechanical engineer.