

Technical Data Sheet



SMART box

Pre-cultivated Sedum SMART box with an interlock system to connect the separate SMART boxes vertically and horizontally to each other. The Sedum Supply Ltd Sedum SMART box are provided with a drainage layer, water buffering layer (approx.. 17.6 l/m²), filter layer, substrate layer and vegetation layer (Sedum).

Application

Sedum Supply Ltd Green Roof Systems – multi-layered build-up

Dimensions

45 x 49 x 8.5 cm (4.6 SMART box per m²)

Specifications

- Material: Polypropylene, provided with an UV-stabilizer
- Weight dry: 8 kg per SMART box / approx. 35 kg/m²
- Weight saturated: 11 kg per SMART box / approx. 48 kg/m²

Sedum species

Sedum acre, Sedum album “Coral Carpet”,
 Sedum floriferum “Weihenstephaner Gold”,
 Sedum hispanicum,
 Sedum reflexum,
 Sedum rupestre,
 Sedum sexangulare,
 Sedum spurium “Album Superbum”,
 Sedum spurium “Coccineum” en Sedum spurium “Fuldaglut