



Blue Grey Slate roof

Blue Grey Slate roof

rwp

rwp

2380

950 1738

Old opening infilled with coursed sandstone taken from the blocked up windows on Havelock Street and the stone panel adjacent.

Form a door opening in the stone panel using the jambs and lintel from Havelock Street. The coursed stone removed is to be saved and re-used where required

Window re-opened and a sash style window inserted

Remodel the ex showroom entrance and replace with matching coursed stone a window opening with 150mm wide sandstone jambs, lintel and cill. The sign as been removed along with the high horizontal window and made up to the stone lintel

Remodel the door opening with 150mm jambs, lintel and door step in sandstone. Timber framed door casing with a fanlight and a roc door in six panel style

The existing shop facade will be retained at this moment of time, but the upper level of the windows will have opening lights inserted

Proposed Details of Bank Street Development Padham,

All first floor windows to be replaced with UPVC mock sash windows, double glazed to the latest standard

Proposed Front Elevation

August 2023
Scale 1 : 50+
JSA - 23 - 11