



Sandstone Copings

Blue Grey Slate roof, stripped back, refelted with breathable membrane, new tanalised battens and re slated

Sandstone Copings

Lead lined sandstone gutters

Coursed Rubble

Coursed Sandstone with dressed flat face

Original window openings infilled with coursed sandstone many years ago

rwp

rwp

Service Entrance to rear  
Rear Yard Wall with car parking in front

Ex doorway stone jambs, lintels and step removed and reused on the front elevation, opening re stoned up to match with stone from newly opened windows

Solid six panel door of clients choice

UPVC windows in the style of Sash frames with top opening light

Proposed Details of Havelock Street Padham, part of Bank Street Project

July 2023  
Scale 1 : 50th  
JSA - 23 - 112M

# Havelock Street Elevation