

RAINWATER GOODS - 1251

Gutters:

1. Supply and fix new cast iron rainwater goods to new and existing roofs including:
2. 100mm ogee gutters to include stop ends and 63mm outlet at lean to and canopy;
3. 100mm ogee gutters to include stop ends, 90° angle and 75mm outlet at extension:
4. 100mm half-round gutters including stop ends and 63mm outlets to main cottage roof;
5. 63mm rainwater pipes generally to include offsets and shoes; 1 No. short 75mm rainwater pipe at west hopper at extension.
6. 1 No. J & JW Longbottom cast iron hopper, pattern No. 80 27" long at east side of extension; 1 No. J & JW Longbottom cast iron hopper, pattern No. 9" at west side of extension.
7. Supply and fix code 6 lead stormwater deflector to stop overspill of stormwater at the west hopper.

Rainwater Goods and cast iron grate

2 Coats Zinsser Allcoat Exterior
Satin, colour **RAL 7022**