














Station Name: **St Helens Junction**

Item Ref:	Link to 360 location online	Works Description	NTL Design Guide Ref:	Location Image	Asset List:	Approximate Quantities / Specification
2.10.1/ 2.10.2	<a href="https://tourmkr.com/F1xstBCfWN/35968030p&amp;229.66h&amp;84.01t">https://tourmkr.com/F1xstBCfWN/35968030p&amp;229.66h&amp;84.01t</a>	Induction loop and Help Point on Platform 1	17.2		Help Point	Replace existing help point with combined induction/help point for Platform 1. Utilise existing power and comms cables. Fix to wall in accordance to SISS specification
2.10.3,2.10.4	<a href="https://tourmkr.com/F1xstBCfWN/35967950p&amp;76.41h&amp;79.63t">https://tourmkr.com/F1xstBCfWN/35967950p&amp;76.41h&amp;79.63t</a>	Induction loop and Help Point on Platform 2	17.2		Help Point	Replace existing help point with combined induction/help point for Platform 2. Utilise existing power and comms cables. Fix to existing post or allow for a new post in accordance to SISS specification
2.10.5	<a href="https://tourmkr.com/F1xstBCfWN/35967998p&amp;151.33h&amp;105.53t">https://tourmkr.com/F1xstBCfWN/35967998p&amp;151.33h&amp;105.53t</a>	Station Map & Key Local Info Board at Platform 1 entrance	A.v1.2		Signage	Replace existing station plan / signage with free issue from NTL in existing frames. Wayfinding signage around the station to be upgraded / enhanced to bring up to NTL and NR standard. PC to carry out detailed survey and design for the station signage. Lump sum with number of signs to be provided as part of the tender.
2.10.6	<a href="https://tourmkr.com/F1xstBCfWN/35967945p&amp;248.99h&amp;94.23t">https://tourmkr.com/F1xstBCfWN/35967945p&amp;248.99h&amp;94.23t</a>	Station Map & Key Local Info Board at (second) Platform 1 entrance	A.v1.2		Signage	Replace existing station plan / signage with free issue from NTL in existing frames. Wayfinding signage around the station to be upgraded / enhanced to bring up to NTL and NR standard. PC to carry out detailed survey and design for the station signage. Lump sum with number of signs to be provided as part of the tender.
2.10.7	<a href="https://tourmkr.com/F1xstBCfWN/35967984p&amp;89.19h&amp;70.84t">https://tourmkr.com/F1xstBCfWN/35967984p&amp;89.19h&amp;70.84t</a>	Station Map & Key Local Info Board at Platform 2 entrance	A.v1.2		Signage	Replace existing station plan / signage with free issue from NTL in existing frames. Wayfinding signage around the station to be upgraded / enhanced to bring up to NTL and NR standard. PC to carry out detailed survey and design for the station signage. Lump sum with number of signs to be provided as part of the tender.

Station Name: **St Helens Junction**

Item Ref:	Link to 360 location online	Works Description	NTL Design Guide Ref:	Location Image	Asset List:	Approximate Quantities / Specification
2.10.8	<a href="https://tourmkr.com/F1xstBCfWN/35967945p&amp;248.99h&amp;94.23t">https://tourmkr.com/F1xstBCfWN/35967945p&amp;248.99h&amp;94.23t</a>	Braille Station Maps on Platform 1 entrance	A.v1.2		Signage	New frame and posts for Braille Station Maps. Maps to be designed and produced by Contractor.
2.10.9	<a href="https://tourmkr.com/F1xstBCfWN/35967984p&amp;89.19h&amp;70.84t">https://tourmkr.com/F1xstBCfWN/35967984p&amp;89.19h&amp;70.84t</a>	Braille Station Maps on Platform 2 entrance	A.v1.2		Signage	New frame and posts for Braille Station Maps. Maps to be designed and produced by Contractor. - re-use existing frames
2.10.10	<a href="https://tourmkr.com/F1xstBCfWN/35967998p&amp;150.48h&amp;105.49t">https://tourmkr.com/F1xstBCfWN/35967998p&amp;150.48h&amp;105.49t</a>	Braille Station Maps on (second) Platform 1 entrance	A.v1.2		Signage	New frame and posts for Braille Station Maps. Maps to be designed and produced by Contractor. - re-use existing frames.
2.10.11	<a href="https://tourmkr.com/F1xstBCfWN/35967992p&amp;335.25h&amp;7https://tourmkr.com/F1xstBCfWN/35968000p&amp;351.94h&amp;80.51t6.13t">https://tourmkr.com/F1xstBCfWN/35967992p&amp;335.25h&amp;7https://tourmkr.com/F1xstBCfWN/35968000p&amp;351.94h&amp;80.51t6.13t</a>	New Accessible W/C & Baby Change Facilities	21.1		Toilet POD	Toilet pod located behind the seats and adjacent Amazon pick up lockers. Power, water and comms from ticket office. Drainage assumed in front of the building within 30m. Assumed area has sufficient lighting and CCTV. PC to confirm.
2.10.12	<a href="https://tourmkr.com/F1xstBCfWN/35968019p&amp;340.8h&amp;73.86t">https://tourmkr.com/F1xstBCfWN/35968019p&amp;340.8h&amp;73.86t</a>	Covered Drop Off/Pick Up Point	7.1		Drop Off	Reconfigure existing drop off for 7m long 1 car covered drop off. Install drop kerbs and reline. Size and manufacturer to be confirmed by the PC.
2.10.13	<a href="https://tourmkr.com/F1xstBCfWN/35967971p&amp;6.86h&amp;80.75t">https://tourmkr.com/F1xstBCfWN/35967971p&amp;6.86h&amp;80.75t</a>	Carpark Resurfacing / Relineing	3.1, 6.1, 13.1		Car Park	Car park requires minor relining. Area 500m2

Station Name: **St Helens Junction**

Item Ref:	Link to 360 location online	Works Description	NTL Design Guide Ref:	Location Image	Asset List:	Approximate Quantities / Specification
2.10.14	<a href="https://tourmkr.com/F1xstBCfWN/35968019p&amp;340.8h&amp;73.86t">https://tourmkr.com/F1xstBCfWN/35968019p&amp;340.8h&amp;73.86t</a>	Footpath / Drop kerb improvements /Ramps	3.3, 6.4, 13.1, 18.2, 18.2, 19.1		Drop Off	Drop kerb at the covered drop off location, 10m long
2.10.15	<a href="https://tourmkr.com/F1xstBCfWN/35968035p&amp;56.11h&amp;72.2t">https://tourmkr.com/F1xstBCfWN/35968035p&amp;56.11h&amp;72.2t</a>	Handrail Tactiles & Stair Nosings on Platform 1	6.3, 6.5, 13.1, 18.1, 18.2, 19.1		Stairs	Stair nosings to be deep cleaned / painted / repaired / replaced (100%). Handrails to be painted to DFT standard yellow. Approximate length of stairs 30m
2.10.16	<a href="https://tourmkr.com/F1xstBCfWN/35967986p&amp;70.24h&amp;74.8t">https://tourmkr.com/F1xstBCfWN/35967986p&amp;70.24h&amp;74.8t</a>	Handrail Tactiles & Stair Nosings on Platform 2	6.3, 6.5, 13.1, 18.1, 18.2, 19.1		Stairs	Stair nosings to be deep cleaned / painted / repaired / replaced (100%). Handrails to be painted to DFT standard yellow. Approximate length of stairs 30m
2.10.17	<a href="https://tourmkr.com/F1xstBCfWN/35968038p&amp;183.09h&amp;71.72t">https://tourmkr.com/F1xstBCfWN/35968038p&amp;183.09h&amp;71.72t</a>	Entrance Doors Matting & Door entrances	1, 2.2, 20.2, 21.1 24.2, 24.6, 27.4		Door Mat	Door matting to be installed. 4m2
2.10.18	<a href="https://tourmkr.com/F1xstBCfWN/35968038p&amp;183.09h&amp;71.72t">https://tourmkr.com/F1xstBCfWN/35968038p&amp;183.09h&amp;71.72t</a>	Waiting Room / Platform Furniture on Platform 1	9, 13.1, 23		Replace seating.	Replace non compliant seating
2.10.19	<a href="https://tourmkr.com/F1xstBCfWN/35968038p&amp;183.09h&amp;71.72t">https://tourmkr.com/F1xstBCfWN/35968038p&amp;183.09h&amp;71.72t</a>	Waiting Room / Platform Furniture on Platform 1	9, 13.1, 23		Replace seating.	Replace non compliant seating
2.10.20	<a href="https://tourmkr.com/F1xstBCfWN/35968020p&amp;107.48h&amp;75.54t">https://tourmkr.com/F1xstBCfWN/35968020p&amp;107.48h&amp;75.54t</a>	Waiting Room / Platform Furniture on Platform 2	9, 13.1, 23		Replace Seating	Replace non compliant seating
2.10.21	<a href="https://tourmkr.com/F1xstBCfWN/35968000p&amp;55.86h&amp;78.39t">https://tourmkr.com/F1xstBCfWN/35968000p&amp;55.86h&amp;78.39t</a>	Waiting Room / Platform Furniture on Platform 2	9, 13.1, 23		Replace seating.	Replace non compliant seating

Station Name: **St Helens Junction**

Item Ref:	Link to 360 location online	Works Description	NTL Design Guide Ref:	Location Image	Asset List:	Approximate Quantities / Specification
2.10.22	<a href="https://tourmkr.com/F1xstBCfWN/35967956p&amp;128.1h&amp;88.13t">https://tourmkr.com/F1xstBCfWN/35967956p&amp;128.1h&amp;88.13t</a>	Reconfigure Waiting Shelter on Platform 2	9, 13.1, 23		Waiting Shelter seating	Reconfigure existing waiting shelter (1 No) replace existing seating. Existing waiting shelter to be painted in accordance with NTL design guide where possible. Powder coated and aluminium waiting shelters to remain as existing as painting repairs will not be possible. PC to confirm.
2.10.23	<a href="https://tourmkr.com/F1xstBCfWN/35967959p&amp;330.76h&amp;89.69t">https://tourmkr.com/F1xstBCfWN/35967959p&amp;330.76h&amp;89.69t</a>	Furniture Painting / Tapping Rails / Window Manifestations on Platform 1	10.1, 10.2, 10.3		Door entrance	Ticket office entrance walls need to be repaired and painted.
2.10.24	<a href="https://tourmkr.com/F1xstBCfWN/35967942p&amp;357.3h&amp;90.09t">https://tourmkr.com/F1xstBCfWN/35967942p&amp;357.3h&amp;90.09t</a>	Furniture Painting / Tapping Rails / Window Manifestations on Platform 2	10.1, 10.2, 10.3		Signage	Tapping rails to be added to the signage.
2.10.25	<a href="https://tourmkr.com/F1xstBCfWN/35968035p&amp;312.93h&amp;89.4t">https://tourmkr.com/F1xstBCfWN/35968035p&amp;312.93h&amp;89.4t</a>	Furniture Painting / Tapping Rails / Window Manifestations on Platform 2	10.1, 10.2, 10.3		Signage	Tapping rails to be added to the signage.
2.10.26	<a href="https://tourmkr.com/F1xstBCfWN/35968020p&amp;190.5h&amp;88.74t">https://tourmkr.com/F1xstBCfWN/35968020p&amp;190.5h&amp;88.74t</a>	Furniture Painting / Tapping Rails / Window Manifestations on Platform 2	10.1, 10.2, 10.3		Signage	Tapping rails to be added to the signage.
2.10.27	<a href="https://tourmkr.com/F1xstBCfWN/35967992p&amp;92.51h&amp;82.93t">https://tourmkr.com/F1xstBCfWN/35967992p&amp;92.51h&amp;82.93t</a>	Furniture Painting / Tapping Rails / Window Manifestations on Platform 2	10.1, 10.2, 10.3		Signage	Tapping rails to be added to the signage.
2.10.28	<a href="https://tourmkr.com/F1xstBCfWN/35968036p&amp;197.26h&amp;85.25t">https://tourmkr.com/F1xstBCfWN/35968036p&amp;197.26h&amp;85.25t</a>	Furniture Painting / Tapping Rails / Window Manifestations on Platform 2	10.1, 10.2, 10.3		Signage	Tapping rails to be added to the signage.



Station Name: **St Helens Junction**

Item Ref:	Link to 360 location online	Works Description	NTL Design Guide Ref:	Location Image	Asset List:	Approximate Quantities / Specification
2.10.29	N/A	Wayfinding - New Assets -PODS & Drop Offs to NTL/NR Standard	NTL Design guide and NR signage guide NR/GN/CIV/300/01	N/A	N/A	Wayfinding signage around the station to be added in relation to new significant assets installed, WC POD and Covered Drop Off. NTL Design Guide and NR standard to be used. PC to carry out detailed survey at delivery and new signage to be agreed with and signed off by Station Manager. Total price to survey, design, supply and fit with approximate number of signs to be provided in the pricing schedule.